

# District Preliminary Geotechnical Report, State Route 241/State Route 91 Express Lanes Connector Project, Orange County, California

*Prepared for:*

Transportation Corridor Agencies

February 2016

EA 0K9700: 012-ORA-241-PM36.1/39.1, 012-ORA-91-PM14.7/18.9, 08-RIV-91-PM0.0/1.5

*Prepared by*



CH2M HILL, Inc.  
6 Hutton Centre Drive, Suite 700  
Santa Ana, California 92707





# Contents

Section	Page
<b>Signature Page.....</b>	<b>V</b>
<b>Acronyms and Abbreviations .....</b>	<b>VII</b>
<b>1 Introduction .....</b>	<b>1-1</b>
1.1 Project Description and Existing Facilities .....	1-1
1.2 Objective and Scope .....	1-2
<b>2 Pertinent Reports and Investigations .....</b>	<b>2-1</b>
2.1 Pertinent Reports.....	2-1
2.2 Previous Investigations .....	2-2
<b>3 Physical Setting .....</b>	<b>3-1</b>
3.1 Climate .....	3-1
3.2 Topography and Drainage.....	3-1
3.3 Prior Land Use .....	3-1
3.4 Human-made and Natural Features of Engineering and Construction Significance .....	3-1
<b>4 Geologic Setting.....</b>	<b>4-1</b>
4.1 Geology .....	4-1
4.2 Subsurface Conditions .....	4-1
4.3 Faulting and Seismicity .....	4-3
<b>5 Geotechnical Conditions .....</b>	<b>5-1</b>
5.1 Groundwater.....	5-1
5.2 Erosion .....	5-1
5.3 Seismic Hazards .....	5-1
5.3.1 Primary Seismic Hazards .....	5-2
5.3.2 Secondary Seismic Hazards.....	5-2
5.4 Slope Stability .....	5-3
5.5 Excavation Characteristics .....	5-3
5.6 Corrosion Characteristics .....	5-3
5.7 Ground Settlement and Collapsible Soils.....	5-4
5.8 Expansive Materials .....	5-4
5.9 Hazardous Materials .....	5-4
<b>6 Preliminary Recommendations and Conclusions .....</b>	<b>6-1</b>
6.1 Retaining walls .....	6-1
6.2 Cutslope South of Eastbound SR 91 (Station 1488+00 “EB91” Line).....	6-1
6.3 General Earthwork .....	6-1
6.4 Future Geotechnical Exploration and Investigations.....	6-2
<b>7 Limitations .....</b>	<b>7-1</b>
<b>8 References.....</b>	<b>8-1</b>

**Appendixes**

- A Project Layout Maps and Plans
- B As-built Log of Test Boring
- C As-built Geotechnical Maps
- D Caltrans Acceleration Response Spectra
- E Soil Survey Data

**Tables**


- 4-1 Distance to Controlling Faults
- 6-1 Proposed Retaining Walls

**Figures**



- 1-1 Project Location Map
- 4-1 Geologic Map
- 5-1 Seismic Hazards Map

# Signature Page

The following individuals have participated in the preparation of this *District Preliminary Geotechnical Report*, or have completed quality review, or both.



Daniel P. Jankly, P.G., C.E.G.  
Project Geologist/Task Lead



Curt Basnett, P.E., G.E.  
Senior Reviewer





# Acronyms and Abbreviations

°F	degrees Fahrenheit
AASHTO	American Association of State Highway and Transportation Officials
ARS	acceleration response spectra
Caltrans	California Department of Transportation
CDMG	California Division of Mines and Geology - now the California Geological Survey
CH2M	CH2M HILL, Inc.
CIP	Corridor Improvement Project
DPGR	District Preliminary Geotechnical Report
ETC	Eastern Transportation Corridor
h:v	horizontal to vertical
ISA	Initial Site Assessment
K Factor	Soil Erodibility Factor
LOTB	Log of Test Boring
LRFD	load and resistance factor design
mm/year	millimeters per year
Mmax	maximum moment magnitude
MSE	mechanically stabilized earth
OC	Overcrossing
PFR	Preliminary Foundation Report
SR	State Route
USDA	U.S. Department of Agriculture



# Introduction

The Transportation Corridor Agency has retained the Michael Baker International team to provide preliminary engineering services for the Project Approval and Environmental Document phase of the State Route (SR) 241/SR 91 Express Lane Connector Project. The project consists of constructing express lane direct connectors from westbound SR 91 to southbound SR 241 and from northbound SR 241 to eastbound SR 91. A single connector ramp will support these two proposed connector lanes. The project location is shown on Figure 1-1.

The Project Approval and Environmental Document phase of the project includes geotechnical, geologic, and seismic evaluations for the proposed improvements. Results of the CH2M HILL, Inc. (CH2M) preliminary evaluations are summarized in this District Preliminary Geotechnical Report (DPGR).

## 1.1 Project Description and Existing Facilities

The SR 241/SR 91 Express Lanes Direct Connector is an effort to develop a median-to-median connection between the SR 241 and SR 91 express lanes. The project includes new connectors—one lane in each direction. Connectors will bring vehicles from the median of northbound SR 241 to the existing eastbound SR 91 express lanes. The reverse movement will also be accommodated, from the westbound SR 91 express lanes to the median of southbound SR 241. The eastern terminus of the project is at the Coal Canyon interchange on SR 91. The southern terminus is just north of the Windy Ridge Wildlife Crossing overpass on SR 241.

The proposed connector (in each direction) will yield one 12-foot-wide travel lane and one 10-foot-wide shoulder on the outside of the travel lanes. A parallel lane that tapers back into the existing SR 91 express lanes will be needed to support northbound SR 241 to eastbound SR 91 movement. One 12-foot-wide travel lane is proposed along southbound and northbound SR 241; these lanes will replace the existing 10-foot-wide shoulders. New 10-foot-wide shoulders will then be constructed adjacent to the new travel lanes along SR 241. In addition, the eastbound Gypsum Canyon on- and off-ramps will be realigned to support the new express lane direct connector. The project layout is shown in Appendix A.

Structural improvements proposed with the project include the SR 241 Wildlife Undercrossing Widening, the 241/91 Connector Overcrossing (OC) (North), 241/91 Connector OC (South), and the Eastbound Gypsum Canyon Road Undercrossing Widening. In addition, a retaining wall is proposed to accommodate the widening of northbound SR 241 approximately 0.5 mile south of SR 91, and eastbound SR 91 approximately 0.75 mile east of Gypsum Canyon Road. Mechanically stabilized earth (MSE) walls are planned along the median of SR 91 to support the connector approach.

Roadway improvements are also proposed along the outside eastbound lanes of SR 91. This will include realignment of the Gypsum Canyon interchange to accommodate the widening of the SR 91. The interchange would remain in the same configuration.

An additional lane/shoulder will be added along the alignment from the SR 241/SR 91 interchange east, to the end of the proposed improvements at Station 1526+00 ("EB91" Line). This additional lane will require modification of the existing, roughly 140-foot tall, 1.5:1 horizontal to vertical (h:v) cutslope present in the vicinity of Station 1488+00, along the south side of SR 91. Based on the current plans, the existing toe of this slope will need to be relocated roughly 50 feet to the south. A 2:1 h:v cutslope with terrace drains is proposed to accommodate the widening in this area. This new slope will have a maximum height on the order of 140 feet, similar to the height of the existing cutslope.

Maximum fill thickness will be approximately 50 feet in the vicinity of Station 515+50 (“241DC5” Line). The project plans showing the proposed improvements are presented in Appendix A.

The project area is currently occupied by improvements related to SR 241 and SR 91. These improvements include the state route mainlines, express lanes, overhead and at-grade connectors, embankment fills, bridges and other associated improvements such as utilities and drainage structures. There are manufactured slopes along most of SR 241 and locally along SR 91. Manufactured fill slopes are generally inclined at 2:1 h:v; cutslopes vary, inclined between 1.5:1 and 3:1 h:v.

## 1.2 Objective and Scope

The objective of this DPGR is to provide sufficient documentation of the geotechnical, geologic, and seismic conditions to support the project team’s evaluation of the project. To meet this objective, the scope of work for this DPGR includes the following:

- Collect and review available information including geotechnical, geologic, and seismic data.
- Conduct field reconnaissance to observe the existing site conditions.
- Evaluate the collected data to characterize the subsurface conditions and identify potential geologic hazards along the alternatives.
- Prepare this DPGR to present findings and preliminary geotechnical recommendations for the next phase of the project.

The recommendations presented in this report are based on existing data collected in the area of, and adjacent to, the project site as discussed in Sections 3 and 4. A project-specific geotechnical investigation was not conducted at the time this report was prepared.



# Pertinent Reports and Investigations

Previous investigations relevant to the project were reviewed to characterize subsurface conditions for the study area. Previous field exploration, as well as other pertinent documents reviewed during this study, are summarized below.

## 2.1 Pertinent Reports

A review was conducted of readily available reports and publications from various public and private files addressing the surface and subsurface conditions in the study area. Geologic and geotechnical information were compiled by acquiring reports and publications from the agencies including, Caltrans, the U.S. Geological Survey, and the California Geological Survey (formerly the California Division of Mines and Geology [CDMG])

The general geologic and fault conditions for the study area were evaluated using the *Geologic Map of the Santa Ana 30' X 60' Quadrangle, California* (Morton, 2004). This map was used as the base for the projects Geologic Map (Figure 4-1).

Pertinent documents were collected and reviewed in preparation of this report, including the following:

- California Department of Transportation (Caltrans). 1973. *As-Built LOTB, Gypsum Canyon Road Undercrossing, Bridge No. 55-506R/L, Orange County*. April 11.
- California Department of Transportation (Caltrans). *As-Built LOTB, Gypsum Canyon Road Undercrossing (Widen), Bridge No. 55-506R/L, Orange County*. March 6.
- Transportation Corridor Agencies. (TCA). 1999. *As-built LOTB, Windy Ridge Wildlife Undercrossing, Bridge No. 55-724 R/L, Orange County*. February 4.
- Transportation Corridor Agencies. (TCA). 2010. *As-built LOTB, Windy Ridge Wildlife Undercrossing (Widen), Bridge No. 55-724 R, Orange County*. March 29.
- Transportation Corridor Agencies. (TCA). 1995. *As-built LOTB, WS Connector Overcrossing, Bridge No. 55-794F, Orange County*. June 1.
- Transportation Corridor Agencies. (TCA). 1996. *As-built LOTB, N241/E91 Connector OC, Bridge No. 55-791G, Orange County*. January 9.
- URS Corporation (URS). 2014. *Final Geotechnical Design Report, SR 91 Corridor Improvement Project (CIP), Design Build Project – Package A. Orange County, California*. 12-OR-91-PM R17.34 to R18.91, EA 0F5404. May 9.
- Silverado Constructors (Silverado). 1999a. *Final Geotechnical Certification Report, Design Sections 11, 12 South and a Portion of 12 North from Stations 650+00 to 821+00, Eastern Transportation Corridor, Orange County, California*. January 15.
- Silverado Constructors (Silverado). 1999b. *Revised Final Geotechnical Certification Report, Design Section 12 North (Stations 851+00 to 880+00) and Design Section 13, Eastern Transportation Corridor, Orange County, California*. October 15.

Preliminary Foundation Reports (PFR) have been prepared for the structural improvements proposed in the project, including the: Windy Ridge Wildlife Undercrossing widening, new 241/91 Connector OC (North), new 241/91 Connector OC (South), and Gypsum Canyon Road Undercrossing widening (CH2M, 2015a, 2015b, 2015c, and 2015d). A Preliminary Materials Report for preliminary pavement design has also been prepared for the project (CH2M, 2015e).

## 2.2 Previous Investigations

Previous explorations along the alignment include those associated with preliminary investigations conducted for the initial SR 241 (Eastern Transportation Corridor [ETC] Section 13) construction. The geotechnical explorations conducted for the ETC Section 13 design were conducted prior to construction, (i.e. before approximately 5.2 million cubic yards of cut were made and 2.5 million cubic yards of fill were placed). The subsurface conditions along the alignment discussed in Section 4 are based primarily on ETC Logs of Test Borings (LOTBs) and as-built geotechnical maps (Appendixes B and C respectively).

The eastern portion of the project along SR 91 overlaps with the SR 91 Corridor Improvement Project (CIP), which is a design-build project currently under construction (Caltrans EA 0F5404). The Geotechnical Design Report for the SR 91 CIP Package A (URS, 2014) was reviewed in preparation of this report.

# Physical Setting

This section provides a brief description of the physical setting of the study area. The subsections cover general climate, topography and drainage considerations, prior land use, and human-made and natural features of engineering and construction significance. These conditions will influence the design, construction, and operation of the project.

## 3.1 Climate

Based on data collected from the Western Regional Climate Center (2014) for the period of 1912 to 2013 at the Yorba Linda weather station (approximately 6 miles to the west-northwest of the SR 241/SR 91 interchange), the average annual precipitation is about 14.4 inches per year. Winter storms account for roughly 75 percent of the rainfall in the area, with spring and fall storms accounting for most of the rest. Average monthly temperatures range from an average low of 42 degrees Fahrenheit (°F) in January to an average high of 88°F in August. Daily temperatures can reach over 100°F during summer. Snowfall is very rare, and freeze-thaw conditions are not a concern in this area.

## 3.2 Topography and Drainage

Topography along the alignment is highly variable, ranging from relatively flat areas along the alignment mainlines and within Santa Ana Canyon, to steeply inclined natural slopes adjacent locally to the mainlines. Manufactured slopes are present essentially along the entire SR 241 portion of the alignment. Manufactured fill slopes are generally inclined at 2:1 h:v; manufactured cutslopes vary, inclined between 1.5:1 and 3:1 h:v. Elevations along the mainlines vary from 1,150 feet at the Windy Ridge wildlife crossing, to 420 feet at Gypsum Canyon Road, and 490 feet at Coal Canyon Road. The topography along the alignment is shown on the project plans in Appendix A.

Drainage along the project alignment consists of sheet flow toward engineered drainage units. No permanent standing surface water was observed within the project limits during the site visit. Temporary surface water may be encountered within surface swales, v-ditches, curbs, and gutters during rainfall events.

## 3.3 Prior Land Use

See the Phase I Initial Site Assessment prepared for the project (RBF, 2015).

## 3.4 Human-made and Natural Features of Engineering and Construction Significance

The Santa Ana River is located immediately north of the SR 91 portion of the alignment as seen on Figure 1-1. The Santa Ana River originates in the San Bernardino Mountains and drains to the Pacific Ocean near Newport Beach in Orange County. Prado Dam is an earthen dam that controls flow to the Santa Ana River, and is located approximately 3 miles east of the alignment.

A 1.5:1 h:v cutslope on the order of 140 feet tall is present south of eastbound SR 91 in the vicinity of Stations 1479 to 1494 ("EB91" Line). This slope was constructed in association with the initial SR 241 construction in the mid 1990's. The slope is performing well from a global stability standpoint, however the slope has undergone significant erosion since being constructed. This slope will be regraded to support the proposed design along SR 91.

Numerous subdrains have been constructed within the SR 241 limits (see Section 4.2 and Appendix C), with a number of the subdrains located in areas of the proposed structures.

# Geologic Setting

The data sources discussed in Section 2 were used to describe the general geologic setting in the study area, including regional geology, faulting, and seismicity. This section also identifies potential seismic hazards within the study area. These potential seismic hazards could result in loading conditions that would affect the design and operations of the project.

## 4.1 Geology

The project is located within the Peninsular Ranges geomorphic province of California, characterized by a series of northwest-trending mountains, valleys, and faults, all of which generally parallel the San Andreas Fault system. The Santa Ana Mountains and the Whittier Fault are prime examples of this northwest-trending regional structure. The Santa Ana Mountains are present as a result of uplift related to movement of the San Andreas and its associated faults, such as the Whittier Fault. As shown on the Caltrans Acceleration Response Spectra (ARS) online generated map in Appendix D, the Whittier segment of the Elsinore Fault Zone is the closest active fault to the site, mapped on the north side of Santa Ana Canyon, north of the study area. The Glen Ivy and Chino segments of the Elsinore Fault Zone are also in close proximity to the site as shown in Appendix D. The site is within the northwestern flank of the Santa Ana Mountains. The Santa Ana Mountains are a structural block bounded by the coast on the west and the Whittier-Elsinore fault zone on the east. The western portion of the Santa Ana Mountains block is underlain predominately by alluvial deposits and Tertiary-aged sedimentary rocks.

## 4.2 Subsurface Conditions

Locally, the study area is underlain by: artificial fill placed in association with SR 241 and SR 91, sediments eroded from upland areas and transported and deposited by the Santa Ana River, competent landslide debris (left in place during construction of SR 241), and sedimentary bedrock of the Topanga, Vaqueros/Sespe, and Santiago Formations. Summary descriptions of the geologic units expected within the study area are presented below. The distribution of earth units is shown on the geologic map covering the site (see Figure 4-1). The geology mapped during grading of the subject portion of the ETC is presented in Appendix C.

The following units may be encountered along the alignment:

- **Surficial soils (Alluvial and artificial fill soils):** The artificial fill soils in the upper 5 feet along SR 91 CIP Package A (URS, 2014a) were described as clayey sand and silty sand, both of which contain variable amounts of gravel. The alluvial soil underlying the fills were generally described as unconsolidated interbedded gravels, sands, silts, and clays (Silverado, 1997).
- **Competent Landslide Debris:** During construction of SR 241 (ETC) Sections 12 and 13, numerous landslides were encountered during grading. The landslides were either completely removed or stabilized. The landslide debris left in-place will be similar to the landslides' bedrock units. The bedrock units along the alignment are described below.
- **Topanga Formation:** The Topanga Formation along the alignment consists of marine, yellow-brown, light olive-gray to dark gray massively interbedded, fine- to medium-grained sandstone and siltstone, with minor, sandy, cobble conglomerate beds. Bedding within the unit is generally poorly defined, with cross-bedded sandstone beds present locally (Silverado, 1997). This unit is present along portions of SR 241 within the project area.

- **Vaqueros/Sespe Formation, undifferentiated:** The undifferentiated Vaqueros/Sespe Formation generally consists of interfingering beds of nonmarine and marine, red-brown, green, and gray clayey and silty, fine- to coarse-grained sandstone interbedded with dark, reddish-brown, sandy siltstone and mudstone. The formation is predominantly poorly bedded to massive, with crossbedded sandstone beds present locally. The Vaqueros/Sespe Formation is moderately to well-indurated with some cemented zones (Silverado, 1997). This unit is present along portions of SR 241 within the project area.
- **Santiago Formation:** The Santiago Formation generally consists of light yellow-brown sandstone with some interbedded lenticular siltstone (Silverado, 1997). In general, the unit is thickly to massively bedded. The formation is generally moderately to well-indurated with some cemented zones. The proposed lane additions to eastbound SR 91, roughly 0.5 mile east of Gypsum Canyon Road, will encroach on an existing 1.5:1 h:v cutslope cut into the Santiago Formation.

The following summary of subsurface conditions is based on our site visit and our review of available, existing geotechnical data for ETC Sections 12 North and 13 and the SR 241/SR 91 interchange (Silverado, 1999a, 1999b).

The vicinity of the Windy Ridge Wildlife Undercrossing is underlain by compacted fill over landslide debris and bedrock of the Vaqueros/Sespe and Santiago Formations. The depth of fill below the southbound SR 241 lanes at the wildlife crossing ranges from approximately 50 to 130 feet in thickness. A subdrain has been constructed at the base of this compacted fill, which transects the wildlife crossing from southwest to northeast. At the area of the proposed widening, the subdrain is located up to 130 feet below existing grade.

The SR 241 mainlines, from the wildlife crossing north, to the proposed SR 241/SR 91 Connector OC (South) – Station 515+50 (“241DC5” Line), are underlain by compacted fill over terrace deposits, landslide debris, and bedrock of the Vaqueros/Sespe and Santiago Formations. The depth of fill along this stretch of highway varies from 4 feet in overexcavated cut areas to approximately 150 feet locally in former canyon areas. Numerous subdrains were constructed at the base of the compacted fill in numerous areas along this stretch of the highway.

The area of the proposed 241/91 Connector OC (South) – Stations 515+50 to 521+50 (“241DC5” Line), is mapped as being underlain by compacted fill over alluvial soil, terrace deposits, landslide debris, and bedrock of the Topanga and Vaqueros/Sespe Formations. The depth of fill along this area varies in thickness, up to approximately 115 feet locally in a former canyon area. Two subdrains have been constructed in this area, with one subdrain located at the base of the compacted fill in the canyon fill near the vicinity of Station 515+80. An additional subdrain has been constructed in the vicinity of Station 520+00.

Northeast of the 241/91 Connector OC (South) – Station 521+50 (“241DC5” Line) to Station 528+50, the alignment is mapped as being underlain by compacted fill over bedrock of the Vaqueros/Sespe Formations. The south abutment area of the 241/91 Connector OC (North), (south of Santa Ana Canyon Road, south of Station 531+80) to Station 528+50 is mapped as Topanga Formation bedrock. A subdrain has been constructed in the vicinity of Station 524+00 at the base of the compacted fill, which is on the order of 60 feet in thickness.

A 1.5:1 h:v cutslope is present extending up from Santa Ana Canyon Road at Station 531+80 (“241DC5” Line), this cutslope is mapped as being composed of Topanga Formation and undifferentiated Vaqueros/Sespe Formation bedrock. Based on the current design, the roadway will sit on cut within bedrock from Stations 528+50 to 531+00. The southwestern abutment for the proposed 241/91 Connector OC (North) will be situated in this area. The proposed 241/91 Connector OC (North) will extend northeast from this abutment and connect to SR 91 near Station 547+50. The bridge from the

cutslope to the northeast will be underlain by fill related to SR 91 and the SR 241/SR 91 interchange, overlying alluvial soils in Santa Ana Canyon.

From Station 547+50 (“241DC5” Line) east along SR 91, the proposed connector and subsequent transition to the mainline toll lanes of SR 91 will be underlain by fill related to SR 91, overlying alluvial soils in Santa Ana Canyon.

The proposed eastbound Gypsum Canyon Road undercrossing widening will be underlain by fill related to SR 91, overlying alluvial soils in Santa Ana Canyon.

The proposed improvements require modification of the existing roughly 140-foot tall, 1.5:1 h:v cutslope present in the vicinity of Station 1488+00 (“EB91” Line), along the south side of SR 91. This slope is composed of Terrace Deposits above Santiago Formation bedrock. Bedding planes within the Terrace Deposits are expected to be limited and subhorizontally dipping. Beds within the Santiago Formation exposed on this slope are variable, but generally trend north 10 degrees west to north 30 degrees west and dip 30 to 60 degrees to the west-southwest. These bedding planes, when intersected with the existing slope face, exhibit an out-of-slope bedding component on the order of 9 degrees.

### 4.3 Faulting and Seismicity

The study area is not located within an Earthquake Fault Zone, as delineated by the Alquist-Priolo Earthquake Fault Zoning Act of 1972 (CDMG, 2000a). Numerous inactive faults have been mapped in the project area in regional studies and during construction of SR 241 and the SR 241/SR 91 Interchange (Morton, 2004; Silverado, 1999a, 1999b); however, no active faults have been mapped transecting the project area.

The study area is located within a seismically active area in Southern California. The Caltrans ARS Online Tool (Caltrans, 2015) indicates that several active faults are present in the region, as shown in Appendix D, and as listed in Table 4-1. The closest active fault relative to the alignment is the Whittier segment of the Elsinore Fault Zone.





# Geotechnical Conditions

Geotechnical conditions were identified based on the review of past geotechnical information referenced in Section 2. These geotechnical conditions include groundwater, erosion potential, seismic hazards, slope stability, excavation characteristics, and potential geologic hazards.

## 5.1 Groundwater

No surface bodies of water are present within the proposed alignment. The active channel of the Santa Ana River is situated between 250 and 2,000 feet north of the SR 91 centerline. Flow within the Santa Ana River is controlled by Prado Dam, situated roughly 3 miles northeast of the eastern end of the project.

Groundwater levels in the Santa Ana Canyon generally correspond to the elevation of the Santa Ana River bed, which corresponds to a depth greater than 25 feet below the existing SR 91 lanes. Along SR 241, sedimentary bedrock formations and artificial fill are present. The bedrock units are generally considered non-water bearing. However, local seepages do exist with the formation, along fracture/fault zones; and local perched water bodies may be present where permeability contrasts exist within the unit. Seepages, as well as groundwater at the base of the existing fills, are controlled by subdrain systems installed during the original construction of SR 241 (Silverado, 1999a).

According to the *Seismic Hazard Zone Report for the Prado Dam and Black Star Canyon 7.5-Minute Quadrangles* (California Division of Mines and Geology, 2000b, 2000c), historically high groundwater level within the Santa Ana Canyon ranges from less than 10 feet to 40 feet below the ground surface. Historically high groundwater levels are not available for the mountainous portions of the project.

Fluctuations in the groundwater level and soil moisture content variations should be anticipated during and after the rainy season. Irrigation of landscaped areas, nearby construction, and numerous other human-made and natural influences could also cause a fluctuation in local groundwater levels.

## 5.2 Erosion

Erosion occurs when rock and/or soil surfaces are exposed to weathering caused by wind and/or water. The United States Department of Agriculture (USDA) (2015) has delineated Soil Erodibility Factors (K Factors), for the soil units mapped along the alignment. The K Factor provides an indication of how susceptible surface soils are to erosion. The USDA ratings for the soils along the alignment are shown in Appendix E.

In general, a K Factor of 0.05 to 0.20 is considered to have a low susceptibility to erosion; 0.20 to 0.40 is considered moderate and greater than 0.40, high (USDA, 2013). Soils mapped along the alignment have a K Factor ranging from 0.05 to 0.37. Based on the distribution of mapped soil units along the alignment, the project area is considered to have a moderate erosion potential.

## 5.3 Seismic Hazards

Two types of seismic hazards were considered within the study area. The first involved primary hazards from ground rupture and shaking. The second involved secondary hazards, primarily generated by ground shaking.

### 5.3.1 Primary Seismic Hazards

The primary seismic hazards present within the study area include seismic shaking and fault-induced ground rupture.

#### 5.3.1.1 Seismic Shaking

Each of the PFRs (CH2M, 2015a, 2015b, 2015c, 2015d) prepared for the proposed structures contains structure specific seismic recommendations. The following information is for the intersection of SR 241 and SR 91 as shown in Appendix D. Based on the various soil types anticipated within the study area, an average shearwave velocity of 900 feet per second (270 meters per second) was selected for this conceptual level of study. Based on the Caltrans (2015) ARS Online Tool, response spectral analysis was conducted to estimate the ground motions at the site. Results indicate a peak ground acceleration of 0.63 (g = acceleration due to gravity). The average shearwave velocity to be used in the final design will be based on future site-specific data. Seismic data are presented in Appendix D; controlling faults are summarized in Table 4-1.

#### 5.3.1.2 Fault-Induced Ground Rupture

Fault-induced ground rupture could occur where active or potentially active faults cross the project alternatives. At these locations, a potential exists for permanent ground displacement along the fault during an earthquake. The nature of the rupture could be vertical movement, horizontal movement, or some combination of vertical and horizontal movement. There are no known active or potentially active faults that transect the study area (see Section 4.3), the risk of ground rupture along the alignment is considered to be low.

### 5.3.2 Secondary Seismic Hazards

A number of geologic hazards can result from strong ground shaking caused by a seismic event. These hazards range from liquefaction to seismically induced settlements, and are discussed below.

- Liquefaction:** During strong ground-shaking, loose, saturated, cohesionless soils in the upper 50 to 75 feet below ground surface can experience a temporary loss of shear strength and ground deformations can occur. This phenomenon is known as liquefaction. The potential for liquefaction will depend on a combination of soil density, the grain-size distribution, depth below the ground surface, and the location of the water table. Consequences of liquefaction could include loss in bearing capacity of foundations, lateral flow or spreading of the ground, and post-earthquake settlement. The elevated portions of the project area underlain by bedrock and artificial fill over bedrock are not considered susceptible to liquefaction. Historic high groundwater levels in the vicinity of the SR 241/SR 91 interchange and within Santa Ana Canyon along SR 91 have been mapped at 10 to 40 feet below ground surface (CDMG, 2000b, 2000c). These areas have been mapped in a liquefaction Zone of Required Investigation as shown on Figure 5-1.
- Seismically Induced Landslides:** The potential for seismically induced landslides will depend on the steepness of the slope, strength and structure of the soil/rock, groundwater depth and extent, and level of ground shaking. Consequences could include adverse loading on structures located on or adjacent to ground that moves. The steeper portions of the slopes along the subject portions of SR 241 and SR 91 have been mapped in an earthquake-induced landslide Zone of Required Investigation as shown on Figure 5-1. The slopes within the limits of the existing SR 241 improvements have not been included in the Zone of Required Investigation. Landslides/unstable areas were previously located within the SR 241 portion of the project area. However, they have been removed/stabilized during the construction of SR 241. There is one slope along SR 91 which will require significant modification, as discussed in Sections 5.4 and 6.2.

- **Seismically Induced Settlement:** Loose, unsaturated granular soils are susceptible to seismically induced settlement. These settlements can result in total and differential settlement of soils supporting structures, roadways, and utilities. The magnitude of these settlements will depend on the type of structure, the characteristics of the soil below the structure, and the level of ground shaking. In general, soils above the groundwater table may be susceptible to seismically induced settlement, including the sediments within the Santa Ana River channel.
- **Tsunamis and Seiches:** Tsunamis are waves typically generated offshore or within large open bodies of water primarily during subaqueous fault rupture or a subaqueous landslide event. Seiches are waves generated within a large closed body of water, also caused either by subaqueous fault rupture or landslide events, or by ground oscillations from distant earthquakes. The study area is located roughly 20 miles from the Pacific Ocean, and has a minimum elevation over 300 feet. As there are no enclosed bodies of water adjacent to the study area, there is no potential impact to the project due to a tsunami or seiche. However, the SR 91 portion of the alignment is located within the inundation zone associated with a failure of Prado Dam on the City of Anaheim General Plan Dam Inundation Map (City of Anaheim, 2001).

## 5.4 Slope Stability

The stability of a slope depends on the inclination, geology and geologic structure, soil and rock strength, and ground and surface water conditions within the slope. Areas with slopes have a potential hazard from slope failures. In addition, excavating, grading, or fill work during construction might introduce temporary slope stability hazards.

The existing slopes present along the alignment will not be significantly modified by the proposed improvements, with the exception of the existing 1.5:1 h:v cutslope located in the vicinity of SR 91 Station 1488+00 (“EB91” Line). Considering that this slope was cut at a 1.5:1 h:v inclination and is performing well from a global stability standpoint, it is likely that the majority of the bedding is either neutral to, or into, slope and that the out-of-slope bedding component (see Section 4.2) is negligible and does not lend to the instability of the slope. No clay seams or significant planes of weakness were mapped on the slope (see Appendix C). This slope is currently undergoing considerable erosion, due to the nature of the Santiago Formation, and the steep 1.5:1 h:v inclination of this slope. Erosional rills on the order of 1 to 2 feet in depth and 3 to 4 feet in width were observed on the slope during the site reconnaissance conducted in 2011.

## 5.5 Excavation Characteristics

It is expected that the onsite bedrock, including the cutslope proposed at Station 1488 (“EB91” Line), will be rippable using conventional methods and equipment. However, localized beds will likely be encountered that will be marginally rippable. These beds will likely be able to be slowly broken down using a concentrated effort, such as with heavy ripping, percussion hammers, or breakers. Oversized material may be generated from these operations, or may be encountered locally within the alluvial soils or conglomerate beds.

## 5.6 Corrosion Characteristics

Soils are defined as corrosive based on the Caltrans Corrosion Guidelines (Caltrans, 2012).

Soils are considered to be corrosive to structural elements if one or more of the following conditions exist:

- Soluble chloride concentration is greater than or equal to 500 parts per million.
- Soluble sulfate concentration is greater than or equal to 2,000 parts per million.

- The pH is 5.5 or less.

The SR 91 CIP (which includes the eastern portion of the SR 91 segment) Geotechnical Design Report (URS, 2014) indicated that corrosive soils were encountered locally during the investigation. Based on the ETC Section 13 Materials Report (Silverardo, 1997), predominantly noncorrosive materials were encountered during the investigation.

Corrosion testing would be conducted during future phases of the project. During design, a corrosion engineer would review the corrosion data and provide appropriate corrosion design recommendations.

## 5.7 Ground Settlement and Collapsible Soils

Ground settlement can occur when new loads are added to soil, or when a change in water levels results in a decrease in pore water pressures within compressible soils. Collapsible soils consist predominantly of sand- and silt-size particles arranged in a loose “honeycomb” structure. This loose structure is held together by small amounts of water-softening cementing agents, such as clay or calcium carbonate. When the soil becomes wet, these cementing agents soften and the honeycomb structure collapses and generates ground settlement. Both conditions could potentially occur within the study area, in particular within young alluvial sediments such as those which underlie SR 91 in the project area.

## 5.8 Expansive Materials

Expansive soils are clay-rich soils that swell and shrink with wetting and drying. The mineralogy and percentage of clay-sized particles present within a soil determine the potential for expansive behavior. The shrink-swell capacity of expansive soils can result in differential movement beneath foundations. Bedrock units also can exhibit expansive properties due to the clay content within the bedrock. Clay-rich soils and bedrock are locally present within the study area. Expansive soils are not uncommon, and can be exported offsite or mixed with non-expansive soils to yield a material suitable for its intended purpose.

Most of the proposed improvements will be founded in existing or new engineered fill. The existing fills were placed in accordance with Caltrans guidelines, and expansive fills are not anticipated within 4 feet of finished grade.

Between direct connector Stations 528+50 and 531+00 (“241DC5” Line), the alignment will be situated atop cut in the Topanga and Vaqueros/Sespe formations. During the original construction of SR 241, the Vaqueros/Sespe formation was observed to be locally highly expansive. Future geotechnical investigations should evaluate the expansion potential of the Vaqueros/Sespe formation bedrock exposed at or near subgrade.

## 5.9 Hazardous Materials

Please see the Initial Site Assessment prepared for the project (RBF, 2015).

# Preliminary Recommendations and Conclusions

The SR 241/SR 91 Express Lanes Connector Project is considered feasible from a geotechnical standpoint. A generalized discussion of the geologic setting and potential geologic hazards covering the study area is presented in Sections 3 through 5 of this report. The following is a discussion of preliminary planning-level recommendations for the project, design-level geotechnical recommendations will be presented in a future Geotechnical Design Report during the next phase of the project. Preliminary geotechnical recommendations for the proposed structures, including the SR 91 median MSE walls, can be found in the associated PFRs (CH2M, 2015a, 2015b, 2015c, 2015d).

A number of the potential geotechnical hazards discussed in Section 5 of this report, including some secondary seismic hazards such as liquefaction will require additional investigation. These hazards are common to California and can be mitigated by implementing the appropriate design measures. Future geotechnical investigations will provide the needed geotechnical parameters to appropriately design the project to account for the appropriate hazards. The project would be designed in accordance with Caltrans Standard Specifications, which include general earthwork and grading specifications.

## 6.1 Retaining walls

The proposed retaining walls are summarized in Table 6-1 and are shown on the project plans in Appendix A. Retaining walls will be designed in accordance with the LRFD method as specified in the *AASHTO LRFD Bridge Design Specifications* (AASHTO, 2012), and *California Amendments to AASHTO LRFD Bridge Design Specifications* (Caltrans, 2014).

The maximum retaining wall height for the project is on the order of 30 feet. For preliminary planning purposes, Caltrans standard walls and MSE walls appear to be suitable retaining wall types. At the locations where right-of-way is limited soldier pile walls can be considered, dependent on the subgrade materials present. A soil-nail or tieback wall may be required where a retaining wall supports a relatively high cutslope.

## 6.2 Cutslope South of Eastbound SR 91 (Station 1488+00 “EB91” Line)

The maximum cutslope for the project is in the vicinity of Station 1488+00 (“EB91” Line) where a modification to the existing 1.5:1 h:v cutslope is proposed. The existing slope is performing well from a global stability standpoint. The new slope will have a maximum height of 140 feet, similar to the height of the existing cutslope in this area. Considering that the slope height will not increase, and the slope will be regraded at 2:1 h:v inclination with terrace drains, it is anticipated that the slope will be stable. The geology of this slope should be further evaluated during the next phase of the project to confirm that adverse conditions are not present.

## 6.3 General Earthwork

Numerous subdrains have been constructed within SR 241 limits (see Section 4.2 and Appendix C), with a number of the subdrains are located in areas of the proposed structures. The locations of these subdrains in relation to proposed improvements should be evaluated as the project proceeds.

Based on the currently available layout of the proposed improvements, cuts and fills are expected to reach design grades. This grading can be achieved using conventional earthwork methods.

The proposed lane additions along SR 241 and SR 91 will be underlain by artificial fill and bedrock. The existing fills were placed in accordance with TCA and Caltrans guidelines, and expansive fills are not anticipated within 4 feet of finished grade along the mainlines. Bedrock encountered near road grade along the proposed connector may need to be removed or remediated if found to be expansive. Areas of existing fill may need to be processed (scarified, moisture conditioned, and recompacted), or overexcavated, dependent on the actual conditions observed.

Bridge embankments will be composed of sedimentary bedrock or new engineered fill, similar to the existing SR 241/SR 91 mainline connectors. The embankments would be constructed in accordance with Caltrans Standard Specifications.

## 6.4 Future Geotechnical Exploration and Investigations

Additional subsurface investigations will be required as the project proceeds. The purpose of the investigations is to evaluate the subsurface conditions and provide geotechnical information for design and construction of structural foundations and remedial earthwork. The following are recommended explorations for the project:

- **Cutslope south of eastbound SR 91, Station 1488 (“EB91” Line,):** The slope should be investigated to verify that favorable geologic structure exists. Downhole geologic structural data should be collected and evaluated from two locations at the top of the slope, the depth of the borings should extend below the toe of slope.
- **Retaining Walls:** For the retaining wall foundations, subsurface explorations would be conducted in accordance with Section 10.4.2 of the American Association of State Highway and Transportation Officials (AASHTO) Load and Resistance Factor Design (LRFD) *Bridge Design Specifications* (AASHTO, 2012). A minimum of one exploration for each retaining wall is recommended. For retaining walls more than 100 feet in length, exploration points will be spaced every 100 to 200 feet. The depth of exploration will extend at least between one and two times the wall height. For anchored and soil-nailed walls, additional exploration points in the anchorage zone are recommended at a distance of 1.0 to 1.5 times the height of the wall behind the wall, spaced at 100 to 200 feet.
- **Bridge Foundations:** See the PFR (CH2M, 2015a, 2015b, 2015c, 2015d )
- **Roadway Design:** Regularly spaced explorations should be conducted to evaluate the pavement and subsurface soils for pavement design. The depth of exploration should be on the order of 10 feet below grade.

All geotechnical explorations except those performed solely for roadway design should extend through unsuitable strata such as soft, highly compressible soils, peat, highly organic materials, and loose coarse-grained soils to reach competent material of suitable bearing strata.

# Limitations

This DPGR has been prepared for the exclusive use of the Transportation Corridor Agencies and its project partners for specific application to the SR 241/SR 91 Express Lanes Connector Project. The report has been prepared in accordance with generally accepted geological and geotechnical engineering practices. No other warranty, express or implied, is made.

The geotechnical and geological information contained in this report is based on data obtained from review of available sources of information such as geological maps and documents, as-built plans, and previous field investigations within the study area. The logs of soil and rock borings from the available information indicate subsurface conditions only at specific locations and times, and only to the depths penetrated. The borings do not necessarily reflect variations that could exist between locations or possible changes that might take place with time and depth. These variations could change some of the hazards discussed and geotechnical recommendations provided in this report. In addition, information about faulting and seismicity is continually being advanced as new scientific work is carried out. These studies could change the level of hazard from faulting and ground shaking, as well as associated hazards, leading to either reduced or increased hazards. As these discoveries are made, the hazard evaluation for the alternatives may require updating.

In the event that any change in the nature, design, or location of the alternatives occurs, conclusions and recommendations of this report should not be considered valid unless such changes are reviewed, and the conclusions of this report are modified or verified in writing by CH2M's geotechnical staff. CH2M is not responsible for any claims, damages, or liability associated with the reinterpretation or reuse of the subsurface data in this report by others.





# References

- American Association of State Highway and Transportation Officials (AASHTO). 2012. *AASHTO LRFD Bridge Design Specifications*. 2012. 6<sup>th</sup> Edition.
- California Department of Transportation (Caltrans). 1973. *As-Built LOTB, Gypsum Canyon Road Undercrossing, Bridge No. 55-506R/L, Orange County*. April 11.
- California Department of Transportation (Caltrans). 1992. *As-Built LOTB, Gypsum Canyon Road Undercrossing (Widen), Bridge No. 55-506R/L, Orange County*. March 6.
- California Department of Transportation (Caltrans). 2012. *Corrosion Guidelines Version 2.0*. Materials Engineering and Testing Services. November.
- California Department of Transportation (Caltrans). 2014. *California Amendments to AASHTO LRFD Bridge Design Specifications*.
- California Department of Transportation (Caltrans). 2015. *Seismic Design Criteria*. Version 2.3.06. Available at <http://dap3.dot.ca.gov/ARSOnline/index.php>. Accessed on June 8, 2015.
- California Division of Mines and Geology (CDMG). 2000a. *Digital Images of Official Maps of Alquist-Priolo Earthquake Fault Zones of California, Southern Region, CD 2000-003*.
- California Division of Mines and Geology (CDMG). 2000b. *Seismic Hazard Zone Report 046 for the Black Star Canyon 7.5-Minute Quadrangle*.
- California Division of Mines and Geology (CDMG). 2000c. *Seismic Hazard Zone Report 045 for the Prado Dam 7.5-Minute Quadrangle*.
- California Division of Mines and Geology (CDMG). 2001a. *Seismic Hazard Zone Map of the Black Star Canyon 7.5-Minute Quadrangle*. Orange County, California, Official Map Released January 17.
- California Division of Mines and Geology (CDMG). 2001b. *Seismic Hazard Zone Map of the Prado Dam 7.5-Minute Quadrangle*. Official Map Released January 17.
- CH2M HILL, Inc. (CH2M). 2015a. *Preliminary Foundation Report. SR241/SR91 Express Lanes Connector Project, 241-91 Connector OC (North)*. Orange County, California. December.
- CH2M HILL, Inc. (CH2M). 2015b. *Preliminary Foundation Report. SR241/SR91 Express Lanes Connector Project, 241-91 Connector OC (South)*. Orange County, California. December.
- CH2M HILL, Inc. (CH2M). 2015c. *Preliminary Foundation Report. SR241/SR91 Express Lanes Connector Project, Windy Ridge Wildlife Undercrossing*. Orange County, California. December.
- CH2M HILL, Inc. (CH2M). 2015d. *Preliminary Foundation Report. SR241/SR91 Express Lanes Connector Project, Gypsum Canyon Road Undercrossing*. Orange County, California. December.
- CH2M HILL, Inc. (CH2M). 2015e. *Preliminary Materials Report. SR241/SR91 Express Lanes Connector Project*. Orange County, California. December.
- City of Anaheim, 2001. *Seismic and Geologic Hazard Evaluation – General Plan Update*. Ninyo and Moore Project No. 203009001. Date September 11.
- Michael Baker International. 2015. *Project Plans for Construction on State Highway in Orange County. Caltrans District 12, 12-ORA-241 PM 36.1/36.9 and 12-ORA-91 PM 14.7/18.9*. November.
- Morton, D.M. 2004. *Preliminary Digital Geologic Map of the Santa Ana 30' x 60' Quadrangle, Southern California*. Southern California Aerial Mapping Project (SCAMP), Open-File Report 99-172, Version 2.0,

prepared by the United States Geological Survey (USGS) in Cooperation with the California Geological Survey (CGS).

RBF Consulting (RBF). 2015. *2015 SR-241/SR-91 Express Lanes Connector Project Phase I Site Assessment*. EA 0K9700. June.

Silverado Constructors (Silverado). 1999a. *Final Geotechnical Certification Report, Design Sections 11, 12 South and a Portion of 12 North from Stations 650+00 to 821+00, Eastern Transportation Corridor, Orange County, California*, January 15.

Silverado Constructors (Silverado). 1999b. *Revised Final Geotechnical Certification Report, Design Section 12 North (Stations 851+00 to 880+00) and Design Section 13, Eastern Transportation Corridor, Orange County, California*, dated June 19, 1998. Revised October 15.

Silverado Constructors. 1997. *Revised Final Geotechnical Report, Materials Report for Design Section 13, State Route 241*. Design Submittal Number E13GXXC-03. Prepared for the Transportation Corridor Agencies. October 6.

Transportation Corridor Agencies. 1995. *As-built LOTB, WS Connector Overcrossing, Bridge No. 55-794F, Orange County*. June 1.

Transportation Corridor Agencies. 1996. *As-built LOTB, N241/E91 Connector OC, Bridge No. 55-791G, Orange County*. January 9.

Transportation Corridor Agencies. 1999. *As-built LOTB, Windy Ridge Wildlife Undercrossing, Bridge No. 55-724 R/L, Orange County*. February 4.

Transportation Corridor Agencies. 2010. *As-built LOTB, Windy Ridge Wildlife Undercrossing (Widen), Bridge No. 55-724 R, Orange County*. March 29.

U.S. Department of Agriculture (USDA). 2013. State Office of Michigan. *Revised Universal Soil Loss Equation (RUSLE) Technical Guide*. Available at <http://www.iwr.msu.edu/rusle/kfactor.htm>.

U.S. Department of Agriculture (USDA), Soil Conservation Service. 2015. *Web Soil Survey 2.0*. Available at: <http://websoilsurvey.nrcs.usda.gov/app/HomePage.htm>. Accessed on June 9, 2015.

URS Corporation. (URS). 2014a. *Final Geotechnical Design Report, SR 91 Corridor Improvement Project (CIP), Design Build Project – Package A*. Project Number 08000001361. May 9.

URS Corporation. (URS). 2014b. *Materials Report, SR 91 Corridor Improvement Project (CIP), Design Build Project – Package A*. Project Number 08000001361. June 10.

Western Regional Climate Center. 2014. *Western U.S. Climate Historical Summaries*. Accessed on April 10, 2014, available at <http://www.wrcc.dri.edu/cgi-bin/cliMAIN.pl?ca9847>.

Tables



**Table 4-1. Distance to Controlling Faults***SR 241/SR 91 Express Lane Connector Project, Orange County, California*

<b>Fault Name/ Fault Identification Number</b>	<b>Mmax</b>	<b>Slip Rate (mm/year)</b>	<b>R<sub>Jup</sub><sup>a</sup></b>	<b>R<sub>JB</sub><sup>b</sup></b>	<b>R<sub>x</sub><sup>c</sup></b>
Elsinore Fault Zone (Glen Ivy Section)/365	7.7	5	4.46	4.46	2.40
Elsinore Fault Zone (Whittier Section)/352	6.9	2.5	1.83	1.83	1.83
Elsinore Fault Zone (Chino Section)/355	6.6	1	6.13	0.29	8.01

<sup>a</sup> Closest distance (in kilometers) to the fault rupture plane<sup>b</sup> Closest distance (in kilometers) measured as the shortest horizontal distance to the surface projection of the rupture area<sup>c</sup> Horizontal distance (in kilometers) to the fault trace or surface projection

mm/year = millimeters per year

Mmax = maximum moment magnitude

**Table 6-1. Proposed Retaining Walls <sup>a</sup>***SR 241/SR 91 Express Lane Connector Project, Orange County, California*



<b>Station/Line<sup>b</sup></b>	<b>Location</b>	<b>Length (feet)</b>	<b>Maximum Height (feet)</b>	<b>Cut/Fill Wall</b>	<b>Supporting Structure</b>
1441 to 1465/"EB91"	SR 91 Median Westbound	1400	15	Fill	Bridge Approach
1441 to 1465/"EB91"	SR 91 Median Eastbound	1400	15	Fill	Bridge Approach
270 to 296/"241DC3"	SR 91 Median	2600	6	Fill	Roadway and Barrier
1504 to 1514/"EB91"	Slope outside SR 91 Eastbound Outside Shoulder	1200	30	Fill	Roadway Widening
882/"B" to 507/"241DC5"	SR 241 Southbound Median	2500	15	Cut/Fill	Roadway Widening

<sup>a</sup> All measurements are approximate<sup>a</sup> See Appendix A

SR = State Route

Figures







**Figure 1-1**

**Site Location Map**

*District Preliminary Geotechnical Report  
SR 241/SR 91 Express Lanes Connector Project  
Orange County, California*









515+00 ("241DC5" Line) = Approximate Station Number  
1526+00 ("EB91" Line) (for reference only)

Base Map: Morton, 2004

## EXPLANATION




## UNITS



**Figure 4-1**  
**Geologic Map**

District Preliminary Geotechnical Report  
SR 241/SR 91 Express Lanes Connector Project  
Orange County, California





Reference: CDMG, 2001a and 2001b

#### MAP EXPLANATION

##### Zones of Required Investigation:



**Liquefaction** – Areas where historical occurrence of liquefaction, or local geological, geotechnical and ground-water conditions indicate a potential for permanent ground displacements such that mitigation as defined in Public Resources Code Section 2693(c) would be required.



**Earthquake Induced Landslides** – Areas where previous occurrence of landslide movement, or local geological, geotechnical and subsurface water conditions indicate a potential for permanent ground displacements such that mitigation as defined in Public Resources Code Section 2693(c) would be required.



**Figure 5-1**

#### Seismic Hazard Zones Map

*District Preliminary Geotechnical Report*

*SR 241/SR 91 Express Lanes Connector Project*

*Orange County, California*

Source: CGS Seismic Hazard Zones, Black Star Canyon and  
Prado Dam Quadrangles (January 17, 2001), Official Maps

SC0417976.01.07.02.CH SR241\_91\_ELCP\_seismic\_hazard\_zones\_map.ai 2/16

**ch2m**

# Appendix A

## Project Layout Maps and Plans











FIGURE 2  
Sheet 1 of 6

*SR-241/SR-91 Express Lanes Connector*  
**Build Alternative**









# LEGEND

- |   |   |  |
|---|---|--|
| <span style="border: 2px solid red; padding: 2px;"> </span> Project Area (Physical Improvements)  | <span style="border-bottom: 2px solid black; width: 20px; display: inline-block;"></span> Proposed Roadway                                | <span style="background-color: #add8e6; border: 1px solid black; width: 15px; height: 10px; display: inline-block;"></span> Proposed Biofiltration Swale   |
| <span style="background-color: #ffccff; border: 1px solid red; width: 20px; height: 10px; display: inline-block;"></span> Advance Signage Areas   | <span style="border-bottom: 2px solid black; width: 20px; display: inline-block;"></span> Proposed Grading Limits (Slope and Access Road) | <span style="background-color: #90ee90; border: 1px solid black; width: 15px; height: 10px; display: inline-block;"></span> Proposed Media Filter          |
| <span style="border-bottom: 2px dashed orange; width: 20px; display: inline-block;"></span> ETC EIR/EIS Project Area                              | <span style="border-bottom: 2px solid orange; width: 20px; display: inline-block;"></span> Proposed Bridge Structure                      | <span style="border-bottom: 2px solid cyan; width: 20px; display: inline-block;"></span> Proposed Storm Drain Pipe   |
| <span style="border-bottom: 2px dashed blue; width: 20px; display: inline-block;"></span> Existing Caltrans Right-of-Way                          | <span style="border-bottom: 2px solid black; width: 20px; display: inline-block;"></span> Proposed Retaining Wall                         | <span style="border-bottom: 2px dotted cyan; width: 20px; display: inline-block;"></span> Proposed Storm Drain Swale                                       |
| <span style="background-color: #ffff00; border: 1px solid black; width: 20px; height: 10px; display: inline-block;"></span> Proposed Right-of-Way | <span style="border-bottom: 2px solid gray; width: 20px; display: inline-block;"></span> Station Line                                     | <span style="background-color: #00ff00; border: 1px solid black; width: 15px; height: 10px; display: inline-block;"></span> Proposed Storm Drain Structure |
| <span style="border-bottom: 2px dashed blue; width: 20px; display: inline-block;"></span> Existing Wildlife Fencing                               |   |  |



0 200 400  
FEET

SOURCE: Bing (2012); RBF (7/1/2015)

I:\RBF1101\GIS\BuildAlternative.mxd (2/3/2016)





FIGURE 2  
Sheet 3 of 6

*SR-241/SR-91 Express Lanes Connector  
Build Alternative*





bing™



0 200 400  
FEET

SOURCE: Bing (2012); RBF (7/1/2015)

I:\RBF1101\GIS\BuildAlternative.mxd (2/3/2016)

#### LEGEND

- |  |  |   |
|--|--|---|
| <span style="border: 2px solid red; padding: 2px;"> </span> Project Area (Physical Improvements)   | <span style="border-bottom: 2px solid black; width: 50px; display: inline-block;"></span> Proposed Roadway                                 | <span style="background-color: lightblue; border: 1px solid blue; width: 20px; height: 10px; display: inline-block;"></span> Proposed Biofiltration Swale |
| <span style="background-color: pink; border: 1px solid red; width: 20px; height: 10px; display: inline-block;"></span> Advance Signage Areas     | <span style="border-bottom: 2px dashed black; width: 50px; display: inline-block;"></span> Proposed Grading Limits (Slope and Access Road) | <span style="background-color: lightgreen; border: 1px solid green; width: 20px; height: 10px; display: inline-block;"></span> Proposed Media Filter      |
| <span style="border-bottom: 2px dashed orange; width: 50px; display: inline-block;"></span> ETC EIR/EIS Project Area                             | <span style="border-bottom: 2px dashed orange; width: 50px; display: inline-block;"></span> Proposed Bridge Structure                      | <span style="border-bottom: 2px solid cyan; width: 50px; display: inline-block;"></span> Proposed Storm Drain Pipe  |
| <span style="border-bottom: 2px dashed blue; width: 50px; display: inline-block;"></span> Existing Caltrans Right-of-Way                         | <span style="border-bottom: 2px solid black; width: 50px; display: inline-block;"></span> Proposed Retaining Wall                          | <span style="border-bottom: 2px dotted cyan; width: 50px; display: inline-block;"></span> Proposed Storm Drain Swale                                      |
| <span style="background-color: yellow; border: 1px solid black; width: 20px; height: 10px; display: inline-block;"></span> Proposed Right-of-Way | <span style="border-bottom: 2px solid gray; width: 50px; display: inline-block;"></span> Station Line                                      | <span style="background-color: cyan; border: 1px solid cyan; width: 20px; height: 10px; display: inline-block;"></span> Proposed Storm Drain Structure    |
| <span style="border-bottom: 2px dashed blue; width: 50px; display: inline-block;"></span> Existing Wildlife Fencing                              |  |   |





FIGURE 2  
Sheet 4 of 6

SR-241/SR-91 Express Lanes Connector  
Build Alternative





# LEGEND

- |   |   |  |
|---|---|--|
| <span style="border: 2px solid red; padding: 2px;"> </span> Project Area (Physical Improvements)  | <span style="border-bottom: 2px solid black; width: 50px; display: inline-block;"></span> Proposed Roadway                                | <span style="background-color: #add8e6; border: 1px solid black; width: 20px; height: 10px; display: inline-block;"></span> Proposed Biofiltration Swale   |
| <span style="background-color: #ffcc99; border: 1px solid black; width: 20px; height: 10px; display: inline-block;"></span> Advance Signage Areas | <span style="border-bottom: 2px solid black; width: 50px; display: inline-block;"></span> Proposed Grading Limits (Slope and Access Road) | <span style="background-color: #90ee90; border: 1px solid black; width: 20px; height: 10px; display: inline-block;"></span> Proposed Media Filter          |
| <span style="border-bottom: 2px dashed orange; width: 50px; display: inline-block;"></span> ETC EIR/EIS Project Area                              | <span style="border-bottom: 2px solid orange; width: 50px; display: inline-block;"></span> Proposed Bridge Structure                      | <span style="border-bottom: 2px solid cyan; width: 50px; display: inline-block;"></span> Proposed Storm Drain Pipe   |
| <span style="border-bottom: 2px dashed blue; width: 50px; display: inline-block;"></span> Existing Caltrans Right-of-Way                          | <span style="border-bottom: 2px solid black; width: 50px; display: inline-block;"></span> Proposed Retaining Wall                         | <span style="border-bottom: 2px dotted cyan; width: 50px; display: inline-block;"></span> Proposed Storm Drain Swale                                       |
| <span style="background-color: #ffff00; border: 1px solid black; width: 20px; height: 10px; display: inline-block;"></span> Proposed Right-of-Way | <span style="border-bottom: 2px solid grey; width: 50px; display: inline-block;"></span> Station Line                                     | <span style="background-color: #00ffcc; border: 1px solid black; width: 20px; height: 10px; display: inline-block;"></span> Proposed Storm Drain Structure |
| <span style="border-bottom: 2px dashed blue; width: 50px; display: inline-block;"></span> Existing Wildlife Fencing                               |   |  |



0 200 400  
FEET

SOURCE: Bing (2012); RBF (7/1/2015)

I:\RBF1101\GIS\BuildAlternative.mxd (2/3/2016)




FIGURE 2  
Sheet 5 of 6

SR-241/SR-91 Express Lanes Connector  
Build Alternative





# LEGEND

- |   |  |  |
|---|--|--|
| <span style="border: 2px solid red; padding: 2px;"> </span> Project Area (Physical Improvements)  | <span style="border-bottom: 2px solid black; width: 20px; display: inline-block;"></span> Proposed Roadway                                 | <span style="border: 1px dashed blue; padding: 2px;"> </span> Proposed Biofiltration Swale   |
| <span style="background-color: #FFDAB9; border: 1px solid black; width: 20px; height: 10px; display: inline-block;"></span> Advance Signage Areas | <span style="border-bottom: 3px double black; width: 20px; display: inline-block;"></span> Proposed Grading Limits (Slope and Access Road) | <span style="background-color: #90EE90; border: 1px solid black; width: 20px; height: 10px; display: inline-block;"></span> Proposed Media Filter          |
| <span style="border-bottom: 2px dashed orange; width: 20px; display: inline-block;"></span> ETC EIR/EIS Project Area                              | <span style="border-bottom: 2px solid orange; width: 20px; display: inline-block;"></span> Proposed Bridge Structure                       | <span style="border-bottom: 2px solid cyan; width: 20px; display: inline-block;"></span> Proposed Storm Drain Pipe   |
| <span style="border-bottom: 2px dashed blue; width: 20px; display: inline-block;"></span> Existing Caltrans Right-of-Way                          | <span style="border-bottom: 2px solid black; width: 20px; display: inline-block;"></span> Proposed Retaining Wall                          | <span style="border-bottom: 2px dotted cyan; width: 20px; display: inline-block;"></span> Proposed Storm Drain Swale                                       |
| <span style="background-color: yellow; border: 1px solid black; width: 20px; height: 10px; display: inline-block;"></span> Proposed Right-of-Way  | <span style="border-bottom: 2px solid gray; width: 20px; display: inline-block;"></span> Station Line                                      | <span style="background-color: #00FF00; border: 1px solid black; width: 20px; height: 10px; display: inline-block;"></span> Proposed Storm Drain Structure |
| <span style="border-bottom: 2px dashed blue; width: 20px; display: inline-block;"></span> Existing Wildlife Fencing                               |  |  |



0 200 400  
FEET

SOURCE: Bing (2012); RBF (7/1/2015)

I:\RBF1101\GIS\BuildAlternative.mxd (2/3/2016)




FIGURE 2  
Sheet 6 of 6

SR-241/SR-91 Express Lanes Connector  
Build Alternative



H:\pdata\10107774\CADD\Transp\Div\Title\_key\_Notes\7774-KM-01.dgn x mohamed.ghonim 19-NOV-2015 19:00 x


DESIGNED BY	CHECKED BY	REVISOR	DATE
TIM HAILE			



NOTE:  
1. FOR ACCURATE RIGHT OF WAY DATA, CONTACT  
RIGHT OF WAY ENGINEERING AT THE DISTRICT OFFICE.

LINE INDEX

LINE	DESCRIPTION
"B" LINE	ROUTE 241
"241DC1" LINE	ROUTE 241/91 NE Exp CONNECTOR
"241DC2" LINE	ROUTE 241/91 SW Exp CONNECTOR
"241DC3" LINE	ROUTE 241/91 NE Exp CONNECTOR
"241DC4" LINE	ROUTE 241/91 SW Exp CONNECTOR
"241DC5" LINE	ROUTE 241/91 NE/SW Exp CONNECTOR
"GM1" LINE	ROUTE 91 EB GYPSUM CANYON Rd OFF-RAMP
"GM2" LINE	SB GYPSUM CANYON Rd TO ROUTE 91 EB LOOP ON-RAMP
"GM3" LINE	NB GYPSUM CANYON Rd TO ROUTE 91 EB DIRECT ON-RAMP
"241N-E" LINE	ROUTE 241/91 NE CONNECTOR
"EB91" LINE	ROUTE 91 EB
"WB91" LINE	ROUTE 91 WB
"AR1" LINE	ACCESS ROAD



KEY MAP  
NO SCALE

K-1

Dist	COUNTY	ROUTE	POST MILES TOTAL PROJECT	SHEET NO.	TOTAL SHEETS
12, 8	Oran, Riv	241, 91, 91	14.7/18.9, 36.1/39.1, 0.0/1.5		
REGISTERED CIVIL ENGINEER			DATE X/X/XX		
PLANS APPROVAL DATE					
THE STATE OF CALIFORNIA OR ITS OFFICERS OR AGENTS SHALL NOT BE RESPONSIBLE FOR THE ACCURACY OR COMPLETENESS OF SCANNED COPIES OF THIS PLAN SHEET.					
MICHAEL BAKER INTL 14725 ALTON PKWY IRVINE, CA 92618			TRANSPORTATION CORRIDOR AGENCIES 125 PACIFICA, SUITE 100 IRVINE, CA 92618		



x

x mohamed.ghoniim 11-FEB-2016 19:02  
x

x H:\pdata\10107774\CADD\Transp\W\Div\Layout\7774-ST-001.dgn  
x

STATE OF CALIFORNIA - DEPARTMENT OF TRANSPORTATION

CONSULTANT FUNCTIONAL SUPERVISOR

CTrans

CALCULATED-  
DESIGNED BY

REVISD BY

CHECKED BY


DATE REVISED

TIM HAILE

NOTE:

1. FOR ACCURATE RIGHT OF WAY DATA, CONTACT  
RIGHT OF WAY ENGINEERING AT THE DISTRICT OFFICE.

Dist	COUNTY	ROUTE	POST MILES TOTAL PROJECT	SHEET No.	TOTAL SHEETS
12, 8	Oran, Riv	241, 91, 91	36.1/39.1, 14.7/18.9, 0.0/1.5		
REGISTERED CIVIL ENGINEER			X/X/XX DATE		
PLANS APPROVAL DATE					
THE STATE OF CALIFORNIA OR ITS OFFICERS OR AGENTS SHALL NOT BE RESPONSIBLE FOR THE ACCURACY OR COMPLETENESS OF SCANNED COPIES OF THIS PLAN SHEET.			REGISTERED PROFESSIONAL ENGINEER No. _____ Exp. _____ CIVIL STATE OF CALIFORNIA		
MICHAEL BAKER INTL 14725 ALTON PKWY IRVINE, CA 92618			TRANSPORTATION CORRIDOR AGENCIES 125 PACIFICA, SUITE 100 IRVINE, CA 92618		



LAYOUT  
SCALE: 1" = 50'

DRAFT

CURVE DATA				
No.	R	$\Delta$	T	L
(1)	6000.00	16°15'43"	857.23	1702.95

MATCHLINE "B" 827+50  
SEE SHEET L-2

BORDER LAST REVISED 7/2/2010

USERNAME => mohamed.ghoniim  
DGN FILE => 7774-ST-001.dgn

RELATIVE BORDER SCALE  
IS IN INCHES



UNIT 0000

PROJECT NUMBER & PHASE

1200020097

DATE PLOTTED => 11-FEB-2016  
TIME PLOTTED => 19:02  
LAST REVISION  
00-00-14


L-1



H:\pdata\10107774\CADD\Transp\WDiv\Layout\7774-ST-002.dgn  
STATE OF CALIFORNIA - DEPARTMENT OF TRANSPORTATION  
CONSULTANT FUNCTIONAL SUPERVISOR  
TIM HAILE  
CHECKED BY  
CALCULATED-DESIGNED BY  
REVISOR  
DATE  
11-FEB-2016 19:02  
mohamed.ghoni



NOTE:  
1. FOR ACCURATE RIGHT OF WAY DATA, CONTACT  
RIGHT OF WAY ENGINEERING AT THE DISTRICT OFFICE.



Dist	COUNTY	ROUTE	POST MILES TOTAL PROJECT	SHEET No.	TOTAL SHEETS
12, 8	Oran, Riv	241, 91, 91	36.1/39.1, 14.7/18.9, 0.0/1.5		
REGISTERED CIVIL ENGINEER			X/X/XX DATE		
PLANS APPROVAL DATE					
THE STATE OF CALIFORNIA OR ITS OFFICERS OR AGENTS SHALL NOT BE RESPONSIBLE FOR THE ACCURACY OR COMPLETENESS OF SCANNED COPIES OF THIS PLAN SHEET.			REGISTERED PROFESSIONAL ENGINEER No. _____ Exp. _____ CIVIL STATE OF CALIFORNIA		
MICHAEL BAKER INTL 14725 ALTON PKWY IRVINE, CA 92618			TRANSPORTATION CORRIDOR AGENCIES 125 PACIFICA, SUITE 100 IRVINE, CA 92618		

DRAFT

CURVE DATA				
No.	R	$\Delta$	T	L
(1)	6000.00	16°15'43"	857.23	1702.95

LAYOUT  
SCALE: 1" = 50'

L-2

BORDER LAST REVISED 7/2/2010

USERNAME => mohamed.ghoni  
DGN FILE => 7774-ST-002.dgn

RELATIVE BORDER SCALE  
15 IN INCHES



UNIT 0000

PROJECT NUMBER & PHASE


1200020097

DATE PLOTTED => 11-FEB-2016  
TIME PLOTTED => 19:02  
LAST REVISION  
00-00-14



NOTE:  
1. FOR ACCURATE RIGHT OF WAY DATA, CONTACT  
RIGHT OF WAY ENGINEERING AT THE DISTRICT OFFICE.

MATCHLINE "B" 841+50  
SEE SHEET L-2



CURVE DATA				
No.	R	$\Delta$	T	L
(1)	6000.00	16°15'43"	857.23	1702.95
(2)	8000.00	09°18'59"	651.85	1300.83

Dist	COUNTY	ROUTE	POST MILES TOTAL PROJECT	SHEET No.	TOTAL SHEETS
12, 8	Oran Riv	241, 91, 91	36.1/39.1, 14.7/18.9, 0.0/1.5		

REGISTERED CIVIL ENGINEER

DATE

PLANS APPROVAL DATE

THE STATE OF CALIFORNIA OR ITS OFFICERS  
OR AGENTS SHALL NOT BE RESPONSIBLE FOR  
THE ACCURACY OR COMPLETENESS OF SCANNED  
COPIES OF THIS PLAN SHEET.

MICHAEL BAKER INTL  
14725 ALTON PKWY  
IRVINE, CA 92618

TRANSPORTATION CORRIDOR  
AGENCIES  
125 PACIFICA, SUITE 100  
IRVINE, CA 92618

REGISTERED PROFESSIONAL ENGINEER

No.

Exp.

CIVIL

STATE OF CALIFORNIA

LAYOUT  
SCALE: 1" = 50'

MATCHLINE "B" 855+50  
SEE SHEET L-4

DRAFT

L-3







H:\pdata\10107774\CADD\Transp\WDiv\LAYOUT\7774-ST-005.dgn  
STATE OF CALIFORNIA - DEPARTMENT OF TRANSPORTATION  
CONSULTANT FUNCTIONAL SUPERVISOR  
CALCULATED-DESIGNED BY  
CHECKED BY  
REVISOR  
DATE  
mohamed.ghoni  
11-FEB-2016 19:03



TIM HAILE


CHECKED BY

REVISOR

DATE

NOTE:  
1. FOR ACCURATE RIGHT OF WAY DATA, CONTACT  
RIGHT OF WAY ENGINEERING AT THE DISTRICT OFFICE.

MATCHLINE "B" 869+50  
SEE SHEET L-4



MATCHLINE "B" 883+50  
SEE SHEET L-6

Dist	COUNTY	ROUTE	POST MILES TOTAL PROJECT	SHEET No.	TOTAL SHEETS
12, 8	Org, Riv	241, 91, 91	36.1/39.1, 14.7/18.9, 0.0/1.5		

REGISTERED CIVIL ENGINEER  
DATE X/X/XX

PLANS APPROVAL DATE

THE STATE OF CALIFORNIA OR ITS OFFICERS  
OR AGENTS SHALL NOT BE RESPONSIBLE FOR  
THE ACCURACY OR COMPLETENESS OF SCANNED  
COPIES OF THIS PLAN SHEET.

MICHAEL BAKER INTL  
14725 ALTON PKWY  
IRVINE, CA 92618

TRANSPORTATION CORRIDOR  
AGENCIES  
125 PACIFICA, SUITE 100  
IRVINE, CA 92618

REGISTERED PROFESSIONAL ENGINEER  
No. \_\_\_\_\_  
Exp. \_\_\_\_\_  
CIVIL  
STATE OF CALIFORNIA

LAYOUT  
SCALE: 1" = 50'

DRAFT

L-5




H:\pdata\10107774\CADD\Transp\WDIV\Layout\7774-ST-006.dgn mohamed.ghoniim 11-FEB-2016 19:03

DESIGNED BY	CHECKED BY	REVIEWED BY	DATE REVISED
CONSULTANT FUNCTIONAL SUPERVISOR	TIM HAILE		
STATE OF CALIFORNIA - DEPARTMENT OF TRANSPORTATION			



NOTE:  
1. FOR ACCURATE RIGHT OF WAY DATA, CONTACT  
RIGHT OF WAY ENGINEERING AT THE DISTRICT OFFICE.

MATCHLINE "B" 883+50  
SEE SHEET L-5




No.	R	$\Delta$	T	L
(3)	5116.00	06°05'50"	272.47	544.42

LAYOUT  
SCALE: 1" = 50'

DRAFT


L-6

Dist	COUNTY	ROUTE	POST MILES TOTAL PROJECT	SHEET No.	TOTAL SHEETS
12, 8	Ora, Riv	241, 91, 91	36.1/39.1, 14.7/18.9, 0.0/1.5		
REGISTERED CIVIL ENGINEER			X/X/XX DATE		
PLANS APPROVAL DATE					
THE STATE OF CALIFORNIA OR ITS OFFICERS OR AGENTS SHALL NOT BE RESPONSIBLE FOR THE ACCURACY OR COMPLETENESS OF SCANNED COPIES OF THIS PLAN SHEET.					
MICHAEL BAKER INTL 14725 ALTON PKWY IRVINE, CA 92618			TRANSPORTATION CORRIDOR AGENCIES 125 PACIFICA, SUITE 100 IRVINE, CA 92618		

BORDER LAST REVISED 7/2/2010

USERNAME => mohamed.ghoniim  
DGN FILE => 7774-ST-006.dgn

RELATIVE BORDER SCALE  
1/8" = 1' IN INCHES



UNIT 0000

PROJECT NUMBER & PHASE

1200020097

LAST REVISION  
00-00-14  
DATE PLOTTED => 11-FEB-2016  
TIME PLOTTED => 19:03












NOTE:  
1. FOR ACCURATE RIGHT OF WAY DATA, CONTACT  
RIGHT OF WAY ENGINEERING AT THE DISTRICT OFFICE.

CURVE DATA				
No.	R	Δ	T	L
(1)	2000.00	36°24'23"	657.69	1270.83
(12)	1350.00	6°08'59"	72.52	144.90
(13)	3438.00	36°03'54"	1119.23	2164.06
(38)	3030.00	35°44'38"	977.03	1890.26



Dist	COUNTY	ROUTE	POST MILES TOTAL PROJECT	SHEET NO.	TOTAL SHEETS
12, 8	Oran, Riv	241, 91, 91	36.1/39.1, 14.7/18.9, 0.0/1.5		

REGISTERED CIVIL ENGINEER

X/X/XX  
DATE

PLANS APPROVAL DATE

THE STATE OF CALIFORNIA OR ITS OFFICERS  
OR AGENTS SHALL NOT BE RESPONSIBLE FOR  
THE ACCURACY OR COMPLETENESS OF SCANNED  
COPIES OF THIS PLAN SHEET.

MICHAEL BAKER INTL  
14725 ALTON PKWY  
IRVINE, CA 92618

TRANSPORTATION CORRIDOR  
AGENCIES  
125 PACIFICA, SUITE 100  
IRVINE, CA 92618

LAYOUT  
SCALE: 1" = 50'

L-9

BORDER LAST REVISED 7/2/2010

USERNAME => moamed.ghoni  
DGN FILE => 7774-ST-009.dgn

RELATIVE BORDER SCALE  
15 IN INCHES

0 1 2 3

UNIT 0000

PROJECT NUMBER & PHASE

1200020097

LAST REVISION  
00-00-14  
DATE PLOTTED => 11-FEB-2016  
TIME PLOTTED => 19:03

1. FOR ACCURATE RIGHT OF WAY DATA, CONTACT  
RIGHT OF WAY ENGINEERING AT THE DISTRICT OFFICE.

No.	R	$\Delta$	T	L
(1)	2000.00	36°24'23"	657.69	1270.83
(13)	3438.00	36°03'54"	1119.23	2164.06
(14)	3530.00	5°37'51"	173.60	346.92
(15)	215.00	33°12'47"	64.12	124.63
(16)	145.50	179°03'35"	16961.33	454.72
(18)	3827.85	4°29'45"	150.26	300.37
(19)	200.00	69°17'32"	138.21	241.87
(38)	3030.00	35°44'38"	977.03	1890.26

**LAYOUT**  
SCALE: 1" = 50'

**L-10**



1. FOR ACCURATE RIGHT OF WAY DATA, CONTACT  
RIGHT OF WAY ENGINEERING AT THE DISTRICT OFFICE.

No.	R	$\Delta$	T	L
(13)	3438.00	36°03'54"	1119.23	2164.06
(20)	3000.00	2°55'34"	76.63	153.22
(21)	3000.00	3°11'29"	83.57	167.10
(22)	3000.00	3°00'12"	78.65	157.25



**LAYOUT**  
SCALE: 1" = 50'

**L-11**

H:\pdata\10107774\CADD\Transp\WDIV\Layout\7774-ST-012.dgn  
STATE OF CALIFORNIA - DEPARTMENT OF TRANSPORTATION  
mohamed.ghoniim 11-FEB-2016 19:03  
CALCULATED-DESIGNED BY  
CHECKED BY  
REVISOR  
DATE REVISED

10107774  
STATE OF CALIFORNIA  
DEPARTMENT OF TRANSPORTATION

CONSULTANT FUNCTIONAL SUPERVISOR  
TIM HAILE

REVISOR  
DATE REVISED

NOTE:  
1. FOR ACCURATE RIGHT OF WAY DATA, CONTACT  
RIGHT OF WAY ENGINEERING AT THE DISTRICT OFFICE.

Dist	COUNTY	ROUTE	POST MILES TOTAL PROJECT	SHEET NO.	TOTAL SHEETS
12, 8	Oran, Riv	241, 91, 91	36.1/39.1, 14.7/18.9, 0.0/1.5		

REGISTERED CIVIL ENGINEER  
DATE

PLANS APPROVAL DATE

THE STATE OF CALIFORNIA OR ITS OFFICERS  
OR AGENTS SHALL NOT BE RESPONSIBLE FOR  
THE ACCURACY OR COMPLETENESS OF SCANNED  
COPIES OF THIS PLAN SHEET.


MICHAEL BAKER INTL  
14725 ALTON PKWY  
IRVINE, CA 92618

TRANSPORTATION CORRIDOR  
AGENCIES  
125 PACIFICA, SUITE 100  
IRVINE, CA 92618

X/X/XX  
DATE

REGISTERED PROFESSIONAL ENGINEER  
No.  
Exp.  
CIVIL  
STATE OF CALIFORNIA

MATCHLINE "EB91" 1463+50  
SEE SHEET L-11



MATCHLINE "EB91" 1477+50  
SEE SHEET L-13

CURVE DATA				
No.	R	Δ	T	L
(23)	2100.00	2°51'45"	52.47	104.91
(24)	3000.00	3°12'04"	83.83	167.60

LAYOUT  
SCALE: 1" = 50'

DRAFT

L-12



H:\pdata\10107774\CADD\Transp\WDiv\Layout\7774-ST-013.dgn  
STATE OF CALIFORNIA - DEPARTMENT OF TRANSPORTATION  
mohamed.ghoniim 11-FEB-2016 19:03  
CONSULTANT FUNCTIONAL SUPERVISOR  
CALCULATED-DESIGNED BY  
TIM HAILE  
CHECKED BY

REVISOR  
DATE

REVISOR  
DATE

REVISOR  
DATE



REVISOR  
DATE

REVISOR  
DATE

NOTE:  
1. FOR ACCURATE RIGHT OF WAY DATA, CONTACT  
RIGHT OF WAY ENGINEERING AT THE DISTRICT OFFICE.


CURVE DATA				
No.	R	Δ	T	L
(25)	3232.00	03°34'34"	100.75	201.43
(26)	3276.00	03°05'07"	102.27	204.47
(27)	25.00	65°27'12"	16.07	28.56
(28)	26.00	157°22'45"	129.99	71.42
(29)	25.00	94°29'20"	27.04	41.23
(30)	25.00	96°34'33"	28.05	42.14
(31)	100.00	08°30'10"	7.43	14.84
(32)	50.00	24°19'44"	10.78	21.23
(33)	120.00	40°02'14"	43.72	83.85
(34)	450.00	16°44'19"	66.20	131.46

Dist	COUNTY	ROUTE	POST MILES TOTAL PROJECT	SHEET NO.	TOTAL SHEETS
12, 8	Oran, Riv	241, 91, 91	36.1/39.1, 14.7/18.9, 0.0/1.5		
REGISTERED CIVIL ENGINEER			X/X/XX DATE		
PLANS APPROVAL DATE					
THE STATE OF CALIFORNIA OR ITS OFFICERS OR AGENTS SHALL NOT BE RESPONSIBLE FOR THE ACCURACY OR COMPLETENESS OF SCANNED COPIES OF THIS PLAN SHEET.					
MICHAEL BAKER INTL 14725 ALTON PKWY IRVINE, CA 92618			TRANSPORTATION CORRIDOR AGENCIES 125 PACIFICA, SUITE 100 IRVINE, CA 92618		



MATCHLINE "EB91" 1477+50  
SEE SHEET L-12

MATCHLINE "EB91" 1491+50  
SEE SHEET L-14



LAYOUT  
SCALE: 1" = 50'

DRAFT

L-13



1. FOR ACCURATE RIGHT OF WAY DATA, CONTACT  
RIGHT OF WAY ENGINEERING AT THE DISTRICT OFFICE.

No.	R	$\Delta$	T	L
(35)	3000.00	51° 52' 00"	1458.88	2715.73
(36)	3044.00	38° 07' 54"	1052.05	2025.86
(39)	3000.00	57° 24' 04"	1642.49	3005.52

Dist	COUNTY	ROUTE	POST MILES TOTAL PROJECT	SHEET No.	TOTAL SHEET
12, 8	Ora, Riv	241, 91, 91	36.1/39.1, 14.7/18.9, 0.0/1.5		


\_\_\_\_\_ X/X/XX  
 REGISTERED CIVIL ENGINEER DATE

\_\_\_\_\_  
 PLANS APPROVAL DATE

No. \_\_\_\_\_  
 Exp. \_\_\_\_\_  
 CIVIL  
 STATE OF CALIFORNIA

THE STATE OF CALIFORNIA OR ITS OFFICERS  
 OR AGENTS SHALL NOT BE RESPONSIBLE FOR  
 THE ACCURACY OR COMPLETENESS OF SCANNED  
 COPIES OF THIS PLAN SHEET.

MICHAEL BAKER INTL 14725 ALTON PKWY IRVINE, CA 92618	TRANSPORTATION CORRIDOR AGENCIES 125 PACIFICA, SUITE 100 IRVINE, CA 92618
--	--



**LAYOUT**  
SCALE: 1" = 50'

**DRAFT**

**L-14**



x

x mohamed.ghoniim 11-FEB-2016 19:03

x

H:\pdata\10107774\CADD\Transp\W\Div\Layout\7774-ST-015.dgn  
STATE OF CALIFORNIA - DEPARTMENT OF TRANSPORTATION

CONSULTANT FUNCTIONAL SUPERVISOR

CALCULATED-DESIGNED BY

REVISOR BY

CHECKED BY

DATE REVISED

TIM HAILE


CONSULTANT FUNCTIONAL SUPERVISOR

CALCULATED-DESIGNED BY

REVISOR BY

x

NOTE:  
1. FOR ACCURATE RIGHT OF WAY DATA, CONTACT  
RIGHT OF WAY ENGINEERING AT THE DISTRICT OFFICE.



Dist	COUNTY	ROUTE	POST MILES TOTAL PROJECT	SHEET NO.	TOTAL SHEETS
12, 8	Oran, Riv	241, 91, 91	36.1/39.1, 14.7/18.9, 0.0/1.5		

REGISTERED CIVIL ENGINEER  
DATE X/X/XX

PLANS APPROVAL DATE

THE STATE OF CALIFORNIA OR ITS OFFICERS OR AGENTS SHALL NOT BE RESPONSIBLE FOR THE ACCURACY OR COMPLETENESS OF SCANNED COPIES OF THIS PLAN SHEET.

MICHAEL BAKER INTL  
14725 ALTON PKWY  
IRVINE, CA 92618

TRANSPORTATION CORRIDOR AGENCIES  
125 PACIFICA, SUITE 100  
IRVINE, CA 92618

REGISTERED PROFESSIONAL ENGINEER  
No. \_\_\_\_\_  
Exp. \_\_\_\_\_  
CIVIL  
STATE OF CALIFORNIA

LAYOUT  
SCALE: 1" = 50'

DRAFT

L-15

H:\pdata\10107774\CADD\Transp\Div\LAYOUT\7774-ST-016.dgn  
STATE OF CALIFORNIA - DEPARTMENT OF TRANSPORTATION  
mohamed.ghoniim 11-FEB-2016 19:03  
CONSULTANT FUNCTIONAL SUPERVISOR  
TIM HAILE  
DESIGNED BY  
CHECKED BY

x

x

x




NOTE:  
1. FOR ACCURATE RIGHT OF WAY DATA, CONTACT  
RIGHT OF WAY ENGINEERING AT THE DISTRICT OFFICE.

### CURVE DATA

No.	R	$\Delta$	T	L
(39)	3000.00	51°52'00"	1458.88	2715.73
(39)	3000.00	57°24'04"	1642.49	3005.52

Dist	COUNTY	ROUTE	POST MILES TOTAL PROJECT	SHEET No.	TOTAL SHEETS
12, 8	Oran, Riv	241, 91, 91	36.1/39.1, 14.7/18.9, 0.0/1.5		
REGISTERED CIVIL ENGINEER			X/X/XX DATE		
PLANS APPROVAL DATE			No. Exp. CIVIL STATE OF CALIFORNIA		
MICHAEL BAKER INTL 14725 ALTON PKWY IRVINE, CA 92618			TRANSPORTATION CORRIDOR AGENCIES 125 PACIFICA, SUITE 100 IRVINE, CA 92618		



LAYOUT  
SCALE: 1" = 50'


DRAFT

L-16



NOTE:  
1. FOR ACCURATE RIGHT OF WAY DATA, CONTACT  
RIGHT OF WAY ENGINEERING AT THE DISTRICT OFFICE.

CURVE DATA				
No.	R	Δ	T	L
(13)	3438.00	36°03'54"	1119.23	2164.06
(37)	3486.00	4°58'31"	151.44	302.70
(38)	3030.00	35°44'38"	977.05	1890.26



MATCHLINE "EB91" 1435+50  
SEE SHEET L-9

MATCHLINE "GM1" 34+50  
SEE SHEET L-9

Dist	COUNTY	ROUTE	POST MILES TOTAL PROJECT	SHEET No.	TOTAL SHEETS
12, 8	Org, Riv	241, 91, 91	36.1/39.1, 14.7/18.9, 0.0/1.5		
REGISTERED CIVIL ENGINEER			X/X/XX DATE		
PLANS APPROVAL DATE			No. Exp. CIVIL STATE OF CALIFORNIA		
MICHAEL BAKER INTL 14725 ALTON PKWY IRVINE, CA 92618			TRANSPORTATION CORRIDOR AGENCIES 125 PACIFICA, SUITE 100 IRVINE, CA 92618		

LAYOUT  
SCALE: 1" = 50'

## Appendix B

### As-built Log of Test Boring

DIST	COUNTY	ROUTE	POST MILES TOTAL PROJECT	SHEET NO.	TOTAL SHEETS
12	Ora	231			


*Lawrence M. Perko*  
 REGISTERED GEOTECHNICAL ENGINEER

PLANS APPROVAL DATE \_\_\_\_\_

CH2M HILL  
 2510 RED HILL AVENUE  
 SANTA ANA, CA 92705

REGISTERED PROFESSIONAL ENGINEER  
 LAWRENCE M. PERKO  
 No. 2136  
 Exp. 6/30/97  
 GEOTECHNICAL  
 STATE OF CALIFORNIA

The State of California or its officers or agents shall not be responsible for the accuracy or completeness of electronic copies of this plan sheet.







**NOTE:**

BENCHMARK: 3R 61A 80, MSL ELEV. 406.173.  
ABOUT 1.0 MILE EAST ALONG RIVERSIDE FREEWAY  
FROM ITS INTERSECTION WITH GYPSUM CANYON RD.  
TO A CONCRETE BOX CULVERT UNDERCROSSING THE FWY.,  
112.5 FT. SOUTH OF SOUTH EDGE OF PAVED SHOULDER  
OF FWY., ON SOUTH END OF A 7.0 FT. LONG HEADWALL  
OF 6.0 FT. BY 5.0 FT. BOX CULVERT, A DIVISION OF  
HIGHWAYS DISK 2.25 INS. DIA.


PITCHER CORE SAMPLERS WERE USED TO COLLECT SAMPLES FROM BORING RW8517

### LEGEND

-  HOLLOW-STEM AUGER/ROTARY WASH BORING  
 (DONE BY OTHERS)  
 HOLLOW-STEM AUGER/ROTARY WASH  
 BORINGS (DONE BY CH2M HILL)  
 TEST PIT (DONE BY CH2M HILL)



**PLAN**  
SCALE : 1" = 50'



## PROFILE

HORIZONTAL SCALE : 1" = 50'  
VERTICAL SCALE : 1" = 10'

STATIONING  
("WS" LINE)

DRAWN BY J. CRAWLEY

CHECKED BY S. JAGANNATH

CH2M HILL

FIELD INVESTIGATOR  
DATE 4/6/95-6/1/95

TRANSPORTATION  
CORRIDOR AGENCIES

MICHAEL ENDRES

**TCA PROJECT MANAGER**

BRIDGE NO.
55-794F
POST MILE

## WS CONNECTOR OVERCROSSING

## LOG OF TEST BORINGS

2-7






DISREGARD PRINTS BEARING EARLIER REVISION DATES —	
--	--

REVISION DATES (PRELIMINARY STAGE ONLY)									
12	11/1								


SHEET	OF
1	10

ORIGINAL SCALE IN INCHES  
FOR REDUCED PLANS

CU	
EA	



### LEGEND OF BORING OPERATIONS



HOLLOW/BUCKET/ROTARY SAMPLE BORING

<input checked="" type="radio"/>	7. FALLOUT	<input checked="" type="radio"/>	SHIELD THEE FROM RADIATION.
<input type="radio"/>		<input type="radio"/>	LINCOLN IDATED UNDRAINED




GRADED GRAVEL


5+1yr	0 - 15
Very 5+1yr	15 - 30

**NOTE:**

BENCHMARK: 3R 61A 80, MSL ELEV. 406.173.  
ABOUT 1.0 MILE EAST ALONG RIVERSIDE FREEWAY  
FROM ITS INTERSECTION WITH GYPSUM CANYON RD.  
TO A CONCRETE BOX CULVERT UNDERCROSSING THE FWY.,  
112.5 FT. SOUTH OF SOUTH EDGE OF PAVED SHOULDER  
OF FWY., ON SOUTH END OF A 7.0 FT. LONG HEADWALL  
OF 6.0 FT. BY 5.0 FT. BOX CULVERT, A DIVISION OF  
HIGHWAYS DISK 2.25 INS. DIA.

### LEGEND

-  HOLLOW-STEM AUGER/ROTARY WASH BORING  
(DONE BY OTHERS)
-  HOLLOW-STEM AUGER/ROTARY WASH  
BORINGS (DONE BY CH2M HILL)
-  TEST PIT (DONE BY CH2M HILL)



**PLAN**  
SCALE : 1" = 50'

DIST	COUNTY	ROUTE	POST MILES TOTAL PROJECT	SHEET NO.	TOTAL SHEETS
12	Ora	231			



*Lawrence N. Perko*  
REGISTERED GEOTECHNICAL ENGINEER

PLANS APPROVAL DATE \_\_\_\_\_

CH2M HILL  
2510 RED HILL AVENUE  
SANTA ANA, CA 92705

REDUCED PROFESSIONAL ENGINEER  
LAWRENCE N. PERKO  
No. 2136  
Exp. 6/30/97  
GEOTECHNICAL  
STATE OF CALIFORNIA

The State of California or its officers or agents shall not be responsible for the accuracy or completeness of electronic copies of this plan sheet.



## PROFILE

HORIZONTAL SCALE : 1" = 50'  
VERTICAL SCALE : 1" = 10'

STATIONING  
( "WS" LINE)

DRAWN BY	J. CRAWLEY
CHECKED BY	S. JAGANNA

CH2M HILL  
FIELD INVESTIGATOR  
DATE 4/4/95



TRANSPORTATION  
CORRIDOR AGENCIES

MICHAEL ENDRES  
TCA PROJECT MANAGER

BRIDGE NO.
55-794F
POST MILE
39-02

## WS CONNECTOR OVERCROSSING

LOG OF TEST BORINGS

2-9

DISREGARD PRINTS BEARING  
EARLIER REVISION DATES —

REVISION DATES (PRELIMINARY STAGE ONLY)							
2	11/1						

SHEET	OF
2	1

ORIGINAL SCALE IN INCHES  
FOR REDUCED PLANS

CU	
EA	

DIST	COUNTY	ROUTE	POST MILES TOTAL PROJECT	SHEET NO.	TOTAL SHEETS
12	Ora	231			


*Lawrence N. Perko*  
REGISTERED GEOTECHNICAL ENGINEER

PLANS APPROVAL DATE

CH2M HILL  
2510 RED HILL AVENUE  
SANTA ANA, CA 92705

REGISTERED PROFESSIONAL ENGINEER  
LAWRENCE N. PERKO  
No. 2136  
Exp. 6/30/97  
GEOTECHNICAL  
STATE OF CALIFORNIA

The State of California or its officers or agents shall not be responsible for the accuracy or completeness of electronic copies of this plan sheet.




**NOTE:**


BENCHMARK: 3R 61A 80, MSL ELEV. 406.173.  
ABOUT 1.0 MILE EAST ALONG RIVERSIDE FREEWAY  
FROM ITS INTERSECTION WITH GYPSUM CANYON RD.  
TO A CONCRETE BOX CULVERT UNDERCROSSING THE FWY.  
112.5 FT. SOUTH OF SOUTH EDGE OF PAVED SHOULDER  
OF FWY., ON SOUTH END OF A 7.0 FT. LONG HEADWALL  
OF 6.0 FT. BY 5.0 FT. BOX CULVERT, A DIVISION OF  
HIGHWAYS DISK 2.25 INS. DIA.

### LEGEND

- ☒ HOLLOW-STEM AUGER/ROTARY WASH BORING  
(DONE BY OTHERS)
- ☐ HOLLOW-STEM AUGER/ROTARY WASH  
BORINGS (DONE BY CH2M HILL)



**PLAN**  
SCALE : 1" = 50'



## PROFILE

HORIZONTAL SCALE : 1" = 50'  
VERTICAL SCALE : 1" = 10'

STATIONING  
("WS" LINE) 5935

DRAWN BY J. CRAWLEY


CHECKED BY S. JAGANNATH

CH2M HILL

FIELD INVESTIGATOR

DATE 3/30/95

ORIGINAL SCALE IN INCHES  
FOR REDUCED PLANS



TRANSPORTATION  
CORRIDOR AGENCIES

MICHAEL ENDRES

**TCA PROJECT MANAGER**

BRIDGE NO.
------------

55-794F

POST MILE
-----------

39-02	
-------	--

### WS CONNECTOR OVERCROSSING

LOG OF TEST BORINGS 2-11

DISREGARD PRINTS BEARING  
EARLIER REVISION DATES —

[illegible]

SHEET	OF
-------	----

3	10
---	----







DIST	COUNTY	ROUTE	POST MILES TOTAL PROJECT	SHEET NO.	TOTAL SHEETS
12	Ora	231			


*Lawrence N. Perko*  
REGISTERED GEOTECHNICAL ENGINEER

PLANS APPROVAL DATE

CH2M HILL  
2510 RED HILL AVENUE  
SANTA ANA, CA 92705

REGISTERED PROFESSIONAL ENGINEER  
LAWRENCE N. PERKO  
No. 2136  
Exp. 6/30/97  
GEOTECHNICAL  
STATE OF CALIFORNIA

*The State of California or its officers or agents shall not be responsible for the accuracy or completeness of electronic copies of this plan sheet.*




**NOTE:**

BENCHMARK: 3R 61A 80, MSL ELEV. 406.173.  
ABOUT 1.0 MILE EAST ALONG RIVERSIDE FREEWAY  
FROM ITS INTERSECTION WITH GYPSUM CANYON RD.  
TO A CONCRETE BOX CULVERT UNDERCROSSING THE FWY.  
112.5 FT. SOUTH OF SOUTH EDGE OF PAVED SHOULDER  
OF FWY., ON SOUTH END OF A 7.0 FT. LONG HEADWALL  
OF 6.0 FT. BY 5.0 FT. BOX CULVERT, A DIVISION OF  
HIGHWAYS DISK 2.25 INS. DIA.


LEGEND

- ☒ HOLLOW-STEM AUGER/ROTARY WASH BORING  
(DONE BY OTHERS)
- ☐ HOLLOW-STEM AUGER/ROTARY WASH  
BORINGS (DONE BY CH2M HILL)



## PLAN


SCALE : 1" = 50'



## PROFILE

HORIZONTAL SCALE : 1" = 50'  
VERTICAL SCALE : 1" = 10'

STATIONING  
( "WS" LINE ) 5935

CALTRANS DESIGN OVERSIGHT	DRAWN BY	J. CRAWLEY	CH2M HILL	 TRANSPORTATION CORRIDOR AGENCIES	MICHAEL ENDRES TCA PROJECT MANAGER	BRIDGE NO.	WS CONNECTION OVERCROSSING
	CHECKED BY	S. JAGANNATH	FIELD INVESTIGATOR			55-794F	
			DATE 3/29/95			39.02	LOG OF TEST BORINGS 2-15

ORIGINAL SCALE IN INCHES  
FOR REDUCED PLANS

DISREGARD PRINTS BEARING EARLIER REVISION DATES →	REVISION DATES (PRELIMINARY STAGE ONLY)									SHEET	OF
	6/12	11/1								5	10

### LEGEND OF BORING OPERATIONS

NOTES:



















### LEGEND OF EARTH MATERIALS (USCS)

RELATIVE DENSITY AND  
CONSISTENCY CLASSIFICATION

Figure 1 is a line graph with two y-axes and one x-axis. The x-axis is labeled 'FRICTION RATIO' and 'TIP INCLINATION (DEG)'. The left y-axis is labeled 'PRESSURE MEASURED ON TIP ELEMENT' and the right y-axis is labeled 'PRESSURE MEASURED ON BOTTOM ELEMENT'. The graph shows two data series: a solid line for the tip element and a dashed line for the bottom element. Both series show a similar trend with two peaks. The first peak occurs at a friction ratio of approximately 0.1, and the second peak occurs at a friction ratio of approximately 0.3. The pressure measured on the tip element is consistently higher than the pressure measured on the bottom element. The graph is titled 'PRESSURE MEASURED ON TIP ELEMENT' and 'PRESSURE MEASURED ON BOTTOM ELEMENT'.



[illegible]

1. TYPES OF BORINGS	
(B)	BUCKET AUGER
(H)	HOLLOW STEM AUGER
(RW)	ROTARY WASH
(T)	TEST PIT
(C)	CONE PENETROMETER
2. SOIL TEST DESIGNATIONS	
(AL)	ATTERBERG LIMITS
(CA)	CHEMICAL ANALYSIS
(CS)	STEEVE ANALYSIS
(ND)	MAX. DRY DENSITY
(PW)	POCKET PENETROMETER
(R)	R-VALUE
(UC)	UNCONSOLIDATED COMPRESSION
(US)	UNCONSOLIDATED UNOBLAINED DIRECT SHEAR

	CL. LEAN CLAY		SC. CLAYEY GRAVEL
	WM. SILT		SM. WELL-GRADED SAND
	CL. ORGANIC CLAY ON SILT		WM. WELL-GRADED SAND
	WM. FAT CLAY		SM. SILTY SAND
	WM. ELASTIC SILT		SC. CLAYEY SAND
	CLAY ON SILT		SANDSTONE
	WM. WELL-GRADED GRAVEL		SHALE
	GP. POORLY-GRADED GRAVEL		CLAYSTONE
	SM. SILTY GRAVEL		SILTSTONE

ASTM D1586	
Sands and Gravels	
Consistency	Blows/foot
Very loose	0 - 4
Loose	4 - 10
Medium dense	10 - 30
Dense	30 - 50
Very dense	Over 50


5	10
---	----

STATIONING (*WS* LINE)		5945		5950	
CALTRANS DESIGN OVERSIGHT	DRAWN BY	J. CRAWLEY	 CH2M HILL & KLEINFELDER FIELD INVESTIGATOR DATE 4/4/95	 TRANSPORTATION CORRIDOR AGENCIES	MICHAEL ENDRES TEA PROJECT MANAGER
	CHECKED BY	S. JAGANNATH			
	BRIDGE NO. 55-794F POST MILE 39.02				
<b>WS CONNECTOR OVERCROSSING</b> <b>LOG OF TEST BORINGS</b> 2-19					
ORIGINAL SCALE IN INCHES FOR REDUCED PLANS				0	1
				2	3
				CU	EA
DISREGARD PRINTS BEARING EARLIER REVISION DATES →				REVISION DATES (PRELIMINARY STAGE ONLY) 7/26 11/1	
				7	10

BENCHMARK: 3R 61A 80, MSL ELEV. 406.173  
ABOUT 1.0 MILE EAST ALONG RIVERSIDE FREEWAY  
FROM ITS INTERSECTION WITH GYPSUM CANYON RD.  
TO A CONCRETE BOX CULVERT UNDERCROSSING THE FWY.  
112.5 FT. SOUTH OF SOUTH EDGE OF PAVED SHOULDER  
OF FWY., ON SOUTH END OF A 7.0 FT. LONG HEADWALL  
OF 6.0 FT. BY 5.0 FT. BOX CULVERT, A DIVISION OF  
HIGHWAYS DISK 2.25 INS. DIA.

☒ HOLLOW-STEM AUGER/ROTARY WASH BORING  
(DONE BY OTHERS)


☐ HOLLOW-STEM AUGER/ROTARY WASH  
BORINGS (DONE BY CH2M HILL)



GROUND SURFACE ALONG WS  
CONNECTOR OC ("WS" LINE)

## PLAN

SCALE : 1" = 50'



## PROFILE

HORIZONTAL SCALE : 1" = 50'  
VERTICAL SCALE : 1" = 10'

STATIONING  
("WS" LINE)

5945

DRAWN BY J. CRAWLEY

CHECKED BY S. JAGANNATH

CH2M HILL

FIELD INVESTIGATOR

DATE 3/31/95

ORIGINAL SCALE IN INCHES  
FOR REDUCED PLANS

TRANSPORTATION  
CORRIDOR AGENCIES

MICHAEL ENDRES

TCA PROJECT MANAGER

BRIDGE NO.

55-794F

POST MILE	
-----------	--

39.02

### WS CONNECTOR OVERCROSSING

LOG OF TEST BORINGS 2-21

DISREGARD PRINTS BEARING  
EARLIER REVISION DATES —

REVISION DATES (PRELIMINARY STAGE ONLY)

SHEET	OF
-------	----

8	10
---	----



LEGEND OF BORING OPERATIONS


LEGEND OF EARTH MATERIALS (USCS)

RELATIVE DENSITY AND CONSISTENCY CLASSIFICATION (ASTM D1586)


LEGEND OF BORING OPERATIONS


LEGEND OF EARTH MATERIALS (USCS)


RELATIVE DENSITY AND CONSISTENCY CLASSIFICATION (ASTM D1586)



BENCHMARK: 3R 61A 80, MSL ELEV. 406.173.  
ABOUT 1.0 MILE EAST ALONG RIVERSIDE FREEWAY  
FROM ITS INTERSECTION WITH GYPSUM CANYON RD.  
TO A CONCRETE BOX CULVERT UNDERCROSSING THE FWY.  
112.5 FT. SOUTH OF SOUTH EDGE OF PAVED SHOULDER  
OF FWY., ON SOUTH END OF A 7.0 FT. LONG HEADWALL  
OF 6.0 FT. BY 5.0 FT. BOX CULVERT, A DIVISION OF  
HIGHWAYS DISK 2.25 INS. DIA.

 HOLLOW-STEM AUGER/ROTARY WASH BORING  
(DONE BY OTHERS)

 HOLLOW-STEM AUGER/ROTARY WASH BORINGS  
(DONE BY CH2M HILL)





















### LEGEND OF BORING OPERATIONS

NOTES:

### LEGEND OF EARTH MATERIALS (USCS)

RELATIVE DENSITY AND  
CONSISTENCY CLASSIFICATION

1	BUCKET AUGER	H	HOLLOW STEM AUGER
2	ROTARY WASH	T	TEST PIT
3	CONE PENETROMETER		
<b>2. SOIL TEST DESIGNATIONS</b>			
1	ATTENBERG LIMITS	25	CONSOLIDATION
2	CHEMICAL ANALYSIS	25	SEIVE ANALYSIS
3	MAX. DRY DENSITY	25	POCKET PENETROMETER
4	R-VALUE	25	UNCONSOLIDATED UNIFORM COMPRESSION
5	DIRECT SHEAR	25	UNCONSOLIDATED UNIFORM COMPRESSION

	CL. LEAN CLAY		DC. CLAYEY GRAVEL
	MA. SILT		SP. WELL- GRADED SAND
	OL. ORGANIC CLAY OR SILT		SP. POORLY- MIXED SAND
	SH. FAT CLAY		SM. SILTY SAND
	SH. ORGANIC CLAY OR SILT		SC. CLAYEY SAND
	SP. WELL- GRADED GRAVEL		SANDSTONE
	SP. POORLY- GRADED GRAVEL		SHALE
	SP. POORLY- GRADED GRAVEL		CL. LUSTONE
	SH. SILTY GRAVEL		SILTSTONE


Sands and Gravels	
Consistency	Blows/foot
Very loose	0 - 4
Loose	4 - 10
Medium dense	10 - 30
Dense	30 - 50
Very dense	over 50

Clays and Silts	
Consistency	Blows/foot
Very soft	0 - 2
Soft	2 - 4
Firm	4 - 8
Stiff	8 - 15
Very stiff	15 - 30
Hard	over 30

DRAWN BY	J. CRAWLEY
CHECKED BY	S. JAGANNATH

CH2M HILL  
FIELD INVESTIGATOR  
DATE 4/14/95



TRANSPORTATION  
CORRIDOR AGENCIES

MICHAEL ENDRES  
TCA PROJECT MANAGER


BRIDGE NO.	55-794F
POST MILE	39.02

## WS CONNECTOR OVERCROSSING

DISREGARD PRINTS BEARING EARLIER REVISION DATES →	REVISION DATES (PRELIMINARY STAGE ONLY)								SHEET	OF
	6/12	11/1							10	10

ORIGINAL SCALE IN INCHES  
FOR REDUCED PLANS





## NOTE:

BENCHMARK: 3R 61A 80, MSL ELEV. 406.173.  
ABOUT 1.0 MILE EAST ALONG RIVERSIDE FREEWAY  
FROM ITS INTERSECTION WITH GYPSUM CANYON RD.  
TO A CONCRETE BOX CULVERT UNDERCROSSING THE FWY..  
112.5 FT. SOUTH OF SOUTH EDGE OF PAVED SHOULDER  
OF FWY., ON SOUTH END OF A 7.0 FT. LONG HEADWALL  
OF 6.0 FT. BY 5.0 FT. BOX CULVERT, A DIVISION OF  
HIGHWAYS DISK 2.25 INS. DIA.

## LEGEND

- HOLLOW-STEM AUGER/ROTARY WASH BORING  
(DONE BY OTHERS)
- HOLLOW-STEM AUGER/ROTARY WASH  
BORINGS (DONE BY SILVERADO/CH2M HILL)

A ROPE-AND-PULLEY HAMMER WAS USED TO  
DRIVE THE SAMPLERS IN ALL BORINGS

RW8517



N241/E91 CONNECTOR OC

H-8209

BENT 2  
"NE" LINE  
RW8566"NE" 6934+33.07  
"GC1" 42+62.77BENT 3  
6935  
RW8567

H-8210

BENT 4


RW8528

"NE" 6935+57.87  
"GC8" 40+58.54"GC1" LINE  
(FUTURE)

## PLAN

SCALE: 1" = 50'

GROUND SURFACE ALONG "NE" LINE



## PROFILE

HORIZONTAL SCALE: 1" = 50'  
VERTICAL SCALE: 1" = 10'

STATIONING ("NE" LINE)

6927+00 6928+00 6929+00 6930+00 6931+00 6932+00 6933+00 6934+00 6935+00 6936+00 6937+00 6938+00 6939+00

CALTRANS DESIGN OVERSIGHT

DRAWN BY J. CRAWLEY

CHECKED BY J. JAGANNATH

P. BOPP/GEOL.  
J. JAGANNATH/ENGR  
(CH2MHILL)  
FIELD INVESTIGATOR  
DATE 6/1/95 & 1/9/96



TRANSPORTATION  
CORRIDOR AGENCIES

MICHAEL ENDRES  
TCA PROJECT MANAGER

BRIDGE NO.

55-791G

POST MILE

16.27

N241/E91 CONNECTOR OC

LOG OF TEST BORINGS I

DISCARD PRINTS BEARING  
EARLIER REVISION DATES

REVISION DATES (PRELIMINARY STAGE ONLY)

5/97

SHEET OF  
1 6

DIST	COUNTY	ROUTE	POST MILES TOTAL PROJECT	SHEET NO.	TOTAL SHEETS
12	Ora	241			

REGISTERED GEOTECHNICAL ENGINEER  
LAWRENCE M. PERKO  
No. 2136  
Exp. 6/30/97  
STATE OF CALIFORNIA

PLANS APPROVAL DATE

CH2M HILL  
2510 RED HILL AVENUE  
SANTA ANA, CA 92705


The State of California or its officers or agents shall not be responsible for  
the accuracy or completeness of electronic copies of this plan sheet.

THE DATA INCLUDED ON THIS LOG OF TEST  
BORINGS HAS BEEN EXTRACTED FROM THE  
GEOTECHNICAL/MATERIALS REPORT FOR TCA  
CONTRACT NO. E94-01. THIS REPORT WAS  
ISSUED BY KLEINFELDER, INC. ON  
MARCH 17, 1994. CH2M HILL HAS UNDERTAKEN  
A REVIEW OF THE REFERENCED INFORMATION  
AND CONSIDERS IT APPROPRIATE FOR THE  
DESIGN OF NE OVERCROSSING NO. (S) 55-791G.

LEGEND OF BORING OPERATIONS

NOTES:

LEGEND OF EARTH MATERIALS (USCS)

RELATIVE DENSITY AND  
CONSISTENCY CLASSIFICATION  
ASTM D1586 AND SOFTENING (1978)

1. TYPES OF BORINGS
- (A) BUCKET AUGER  
(B) ROTARY WASH  
(C) CONE PENETROMETER  
(D) SOIL TEST DESIGNATIONS
2. SOIL TEST DESIGNATIONS
- (1) ATTERBURG LIMITS  
(2) R-VALUE  
(3) CHEMICAL ANALYSIS  
(4) UNCONSOLIDATED TRIAXIAL  
(5) DIRECT SHEAR  
(6) COMFINED COMPRESSION
3. SOIL TEST DESIGNATIONS
- (7) ATTERBURG LIMITS  
(8) R-VALUE  
(9) CHEMICAL ANALYSIS  
(10) UNCONSOLIDATED TRIAXIAL  
(11) DIRECT SHEAR  
(12) COMFINED COMPRESSION

- LEGEND OF EARTH MATERIALS (USCS)
- CL, LEAN CLAY  
ML, SILT  
OL, ORGANIC CLAY OR SILT  
CH, FAT CLAY  
MH, ELASTIC SILT  
OH, ORGANIC CLAY OR SILT  
SH, SHALE  
CLAYSTONE  
SILTSTONE
- GC, CLAYEY GRAVEL  
GW, WELL-GRADED SAND  
SP, POORLY-GRADED SAND  
SM, SILTY SAND  
SC, CLAYEY SAND  
ST, SANDSTONE  
SH, SHALE  
CLAYSTONE  
SILTSTONE

- RELATIVE DENSITY AND  
CONSISTENCY CLASSIFICATION  
ASTM D1586 AND SOFTENING (1978)
- SOFTNESS AND STIFFNESS
- Consistency
- Very soft  
Soft  
Firm  
Very stiff  
Hard
- Stiffness
- Very soft  
Soft  
Firm  
Very stiff  
Hard






BENCHMARK: 3R 61A 80, MSL ELEV. 406.173.  
ABOUT 1.0 MILE EAST ALONG RIVERSIDE FREEWAY  
FROM ITS INTERSECTION WITH GYPSUM CANYON RD.  
TO A CONCRETE BOX CULVERT UNDERCROSSING THE FWY.,  
112.5 FT. SOUTH OF SOUTH EDGE OF PAVED SHOULDER  
OF FWY., ON SOUTH END OF A 7.0 FT. LONG HEADWALL  
OF 6.0 FT. BY 5.0 FT. BOX CULVERT, A DIVISION OF  
HIGHWAYS DISK 2.25 INS. DIA.

☒ HOLLOW-STEM AUGER/ROTARY WASH BORING  
(DONE BY OTHERS)

☐ HOLLOW-STEM AUGER/ROTARY WASH  
BORINGS (DONE BY SILVERADO/CH2M HILL)

RW8517




*Lawrence M. Perko*  
REGISTERED GEOTECHNICAL ENGINEER

PLANS APPROVAL DATE

CH2M HILL  
2510 RED HILL AVENUE  
SANTA ANA, CA 92705

REGISTERED PROFESSIONAL ENGINEER  
LAWRENCE M. PERKO  
No. 2136  
Exp. 6/30/97  
GEOTECHNICAL  
STATE OF CALIFORNIA

THE DATA INCLUDED ON THIS LOG OF TEST BORINGS HAS BEEN EXTRACTED FROM THE GEOTECHNICAL/MATERIALS REPORT FOR TCA CONTRACT NO. E94-01. THIS REPORT WAS ISSUED BY KLEINFELDER, INC. ON MARCH 17, 1994. CH2M HILL HAS UNDERTAKEN A REVIEW OF THE REFERENCED INFORMATION AND CONSIDERS IT APPROPRIATE FOR THE DESIGN OF NE OVERCROSSING NO. (S) 55-791G.



2.4" DIAMETER SAMPLES WERE TAKEN USING A CALIFORNIA SPLIT BARREL SAMPLER WITH AN INSIDE DIAMETER (I.D.) OF 2.4" AND AN OUTSIDE DIAMETER (O.D.) OF 3.25".

2.9" DIAMETER SAMPLES WERE TAKEN USING A PITCHER CORE SAMPLER, AND RETAINED IN 2.875" I.D. AND 3.0" O.D. THIN-WALL SAMPLE TUBES.

HORIZONTAL SCALE: 1" = 50'  
VERTICAL SCALE: 1" = 10'

6927+00	6928+00	6929+00	6930+00	6931+00	6932+00	6933+00	6934+00	6935+00	6936+00	6937+00	6938+00	6939+00
---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------

DRAWN BY	J. CRAWLEY
CHECKED BY	J. JAGANNATH

M. AZEEMUDDIN/ENGR.,  
S. JACANNATH/ENGR  
(CH2M HILL)  
FIELD INVESTIGATOR  
DATE 1/10/96 & 1/24/96



TRANSPORTATION  
CORRIDOR AGENCIES

MICHAEL ENDRES  
ICA PROJECT MANAGER

BRIDGE NO.
55-791G
POST MILE
16.27

## N241/E91 CONNECTOR OC

LOG OF TEST BORINGS 3

DISREGARD PRINTS BEARING  
EARLIER REVISION DATES —

REVISION DATES (PRELIMINARY STAGE ONLY)

SHEET	OF
3	6

ORIGINAL SCALE IN INCHES  
FOR REDUCED PLANS

CU	12-240
EA	111000

2-11





# **NOTE:**

BENCHMARK: 3R 61A 80, MSL ELEV. 406.173.  
ABOUT 1.0 MILE EAST ALONG RIVERSIDE FREEWAY  
FROM ITS INTERSECTION WITH GYPSUM CANYON RD.  
TO A CONCRETE BOX CULVERT UNDERCROSSING THE FWY.,  
112.5 FT. SOUTH OF SOUTH EDGE OF PAVED SHOULDER  
OF FWY., ON SOUTH END OF A 7.0 FT. LONG HEADWALL  
OF 6.0 FT. BY 5.0 FT. BOX CULVERT, A DIVISION OF  
HIGHWAYS DISK 2.25 INS. DIA.

## **LEGEND**


- HOLLOW-STEM AUGER/ROTARY WASH BORING (DONE BY OTHERS)
- HOLLOW-STEM AUGER/ROTARY WASH BORINGS (DONE BY SILVERADO/CH2M HILL)

A ROPE-AND-PULLEY HAMMER WAS USED TO  
DRIVE THE SAMPLERS IN ALL BORINGS



## **PLAN**

SCALE: 1" = 50'



## **NOTE:**

2.4" DIAMETER SAMPLES WERE TAKEN USING  
A CALIFORNIA SPLIT BARREL SAMPLER WITH  
AN INSIDE DIAMETER (I.D.) OF 2.4" AND  
AN OUTSIDE DIAMETER (O.D.) OF 3.25".

2.9" DIAMETER SAMPLES WERE TAKEN USING  
A PITCHER CORE SAMPLER, AND RETAINED  
IN 2.875" I.D. AND 3.0" O.D. THIN-WALL  
SAMPLE TUBES.

## **PROFILE**

HORIZONTAL SCALE: 1" = 50'  
VERTICAL SCALE: 1" = 10'

THE DATA INCLUDED ON THIS LOG OF TEST  
BORINGS HAS BEEN EXTRACTED FROM THE  
GEOTECHNICAL/MATERIALS REPORT FOR TCA  
CONTRACT NO. E94-01. THIS REPORT WAS  
ISSUED BY KLEINFELDER, INC. ON  
MARCH 17, 1994. CH2M HILL HAS UNDERTAKEN  
A REVIEW OF THE REFERENCED INFORMATION  
AND CONSIDERS IT APPROPRIATE FOR THE  
DESIGN OF NE OVERCROSSING NO. (S) 55-791G.



DIST	COUNTY	ROUTE	POST MILES TOTAL PROJECT	SHEET TOTAL NO. SHEETS
12	Ora	241		

**REGISTERED GEOTECHNICAL ENGINEER**  
LAWRENCE N. PERKO  
No. 2136  
Exp. 6/30/97  
CH2M HILL  
2510 RED HILL AVENUE  
SANTA ANA, CA 92705

PLANS APPROVAL DATE: \_\_\_\_\_

The State of California or its officers or agents shall not be responsible for the accuracy or completeness of electronic copies of this plan sheet.

DRAWN BY J. CRAWLEY		M. SIERADZKI/KLEINFELDER S. JAGANNATH (ENGR)/ CH2M HILL		TRANSPORTATION CORRIDOR AGENCIES		MICHAEL ENDRES TCA PROJECT MANAGER		BRIDGE NO. 55-791G		N241/E91 CONNECTOR OC	
CHECKED BY J. JAGANNATH		FIELD INVESTIGATOR						POST MILE 16.27		LOG OF TEST BORINGS 4	
DATE 10/23/90 & 1/12/96											
ORIGINAL SCALE IN INCHES FOR REDUCED PLANS		0 1 2 3		CU 12-240 EA 111000		DISREGARD PRINTS BEARING EARLIER REVISION DATES		REVISION DATES (PRELIMINARY STAGE ONLY)		SHEET OF	
								5/97		4 6	




BENCHMARK: 3R 61A 80, MSL ELEV. 406.173.  
ABOUT 1.0 MILE EAST ALONG RIVERSIDE FREEWAY  
FROM ITS INTERSECTION WITH GYPSUM CANYON RD.  
TO A CONCRETE BOX CULVERT UNDERCROSSING THE FWY.  
112.5 FT. SOUTH OF SOUTH EDGE OF PAVED SHOULDER  
OF FWY., ON SOUTH END OF A 7.0 FT. LONG HEADWALL  
OF 6.0 FT. BY 5.0 FT. BOX CULVERT, A DIVISION OF  
HIGHWAYS DISK 2.25 INS. DIA.

☒ HOLLOW-STEM AUGER/ROTARY WASH BORING  
(DONE BY OTHERS)

☐ HOLLOW-STEM AUGER/ROTARY WASH  
BORINGS (DONE BY SILVERADO/CH2M HILL)

A ROPE-AND-PULLEY HAMMER WAS USED TO  
DRIVE THE SAMPLERS IN ALL BORINGS



2.4" DIAMETER SAMPLES WERE TAKEN USING A CALIFORNIA SPLIT BARREL SAMPLER WITH AN INSIDE DIAMETER (I.D.) OF 2.4" AND AN OUTSIDE DIAMETER (O.D.) OF 3.25".

2.9" DIAMETER SAMPLES WERE TAKEN USING A PITCHER CORE SAMPLER, AND RETAINED IN 2.875" I.D. AND 3.0" O.D. THIN-WALL SAMPLE TUBES.

HORIZONTAL SCALE: 1" = 50'  
VERTICAL SCALE: 1" = 10'



ORIGINAL SCALE IN INCHES  
FOR REDUCED PLANS

CU	12-240
EA	111000

	DISREGARD PRINTS BEARING EARLIER REVISION DATES —
--	--

REVISION DATES (PRELIMINARY STAGE ONLY)							
5/97							

	SHEET	OF
	5	6

2-15




## NOTE:

BENCHMARK: 3R 61A 80, MSL ELEV. 406.173.  
ABOUT 1.0 MILE EAST ALONG RIVERSIDE FREEWAY  
FROM ITS INTERSECTION WITH GYPSUM CANYON RD.  
TO A CONCRETE BOX CULVERT UNDERCROSSING THE FWY.,  
112.5 FT. SOUTH OF SOUTH EDGE OF PAVED SHOULDER  
OF FWY., ON SOUTH END OF A 7.0 FT. LONG HEADWALL  
OF 6.0 FT. BY 5.0 FT. BOX CULVERT, A DIVISION OF  
HIGHWAYS DIST 2.25 INS. DIA.


## LEGEND

- HOLLOW-STEM AUGER/ROTARY WASH BORING  
(DONE BY OTHERS)
- HOLLOW-STEM AUGER/ROTARY WASH  
BORINGS (DONE BY SILVERADO/CH2M HILL)

A ROPE-AND-PULLEY HAMMER WAS USED TO  
DRIVE THE SAMPLERS IN ALL BORINGS



PLAN  
SCALE: 1" = 50'



## NOTE:

2.4" DIAMETER SAMPLES WERE TAKEN USING  
A CALIFORNIA SPLIT BARREL SAMPLER WITH  
AN INSIDE DIAMETER (I.D.) OF 2.4" AND  
AN OUTSIDE DIAMETER (O.D.) OF 3.25".

2.9" DIAMETER SAMPLES WERE TAKEN USING  
A PITCHER CORE SAMPLER, AND RETAINED  
IN 2.875" I.D. AND 3.0" O.D. THIN-WALL  
SAMPLE TUBES.


THE DATA INCLUDED ON THIS LOG OF TEST  
BORINGS HAS BEEN EXTRACTED FROM THE  
GEOTECHNICAL/MATERIALS REPORT FOR TCA  
CONTRACT NO. E94-01. THIS REPORT WAS  
ISSUED BY KLEINFELDER, INC. ON  
MARCH 17, 1994. CH2M HILL HAS UNDERTAKEN  
A REVIEW OF THE REFERENCED INFORMATION  
AND CONSIDERS IT APPROPRIATE FOR THE  
DESIGN OF NE OVERCROSSING NO. (S) 55-791G.

## PROFILE

HORIZONTAL SCALE: 1" = 50'  
VERTICAL SCALE: 1" = 10'


STATIONING (\*NE\* LINE)

DRAWN BY J. CRAWLEY		D. CARROLL/KLEINFELDER, S. JAGANNATH (ENGR)/CH2M HILL FIELD INVESTIGATOR		MICHAEL ENDRES TCA PROJECT MANAGER		BRIDGE NO. 55-791G		N241/E91 CONNECTOR OC	
CHECKED BY J. JAGANNATH		DATE 12/17/90 & 1/22/96				POST MILE 16.27		LOG OF TEST BORINGS 6	
ORIGINAL SCALE IN INCHES FOR REDUCED PLANS				CU 12-240 EA 111000		DISREGARD PRINTS BEARING EARLIER REVISION DATES		REVISION DATES (PRELIMINARY STAGE ONLY)	
						5/97		SHEET 6 OF 6	

BRIDGE DEPARTMENT  
ENGINEERING GEOLOGY SECTION

A hand-drawn map of the study area. The map shows the intersection of Route 91 and Gypsum Canyon Road. Route 91 runs horizontally, with 'WEST' and 'EAST BOUND' lanes. Gypsum Canyon Road runs vertically, with 'ROAD' and 'CANYON' labels. The intersection is marked with a circle. Five locations are marked with black dots and labeled: B-1 (bottom left), B-2 (top right), B-3 (middle right), B-5 (top left), and B-6 (middle left). A north arrow is in the upper right corner. A scale bar at the bottom right indicates distances in feet: 0, 100, 200, 300, 400, 500, 600, 700, 800, 900, 1000, 1100, 1200, 1300, 1400, 1500, 1600, 1700, 1800, 1900, 2000, 2100, 2200, 2300, 2400, 2500, 2600, 2700, 2800, 2900, 3000, 3100, 3200, 3300, 3400, 3500, 3600, 3700, 3800, 3900, 4000, 4100, 4200, 4300, 4400, 4500, 4600, 4700, 4800, 4900, 5000, 5100, 5200, 5300, 5400, 5500, 5600, 5700, 5800, 5900, 6000, 6100, 6200, 6300, 6400, 6500, 6600, 6700, 6800, 6900, 7000, 7100, 7200, 7300, 7400, 7500, 7600, 7700, 7800, 7900, 8000, 8100, 8200, 8300, 8400, 8500, 8600, 8700, 8800, 8900, 9000, 9100, 9200, 9300, 9400, 9500, 9600, 9700, 9800, 9900, 10000, 10100, 10200, 10300, 10400, 10500, 10600, 10700, 10800, 10900, 11000, 11100, 11200, 11300, 11400, 11500, 11600, 11700, 11800, 11900, 12000, 12100, 12200, 12300, 12400, 12500, 12600, 12700, 12800, 12900, 13000, 13100, 13200, 13300, 13400, 13500, 13600, 13700, 13800, 13900, 14000, 14100, 14200, 14300, 14400, 14500, 14600, 14700, 14800, 14900, 15000, 15100, 15200, 15300, 15400, 15500, 15600, 15700, 15800, 15900, 16000, 16100, 16200, 16300, 16400, 16500, 16600, 16700, 16800, 16900, 17000, 17100, 17200, 17300, 17400, 17500, 17600, 17700, 17800, 17900, 18000, 18100, 18200, 18300, 18400, 18500, 18600, 18700, 18800, 18900, 19000, 19100, 19200, 19300, 19400, 19500, 19600, 19700, 19800, 19900, 20000, 20100, 20200, 20300, 20400, 20500, 20600, 20700, 20800, 20900, 21000, 21100, 21200, 21300, 21400, 21500, 21600, 21700, 21800, 21900, 22000, 22100, 22200, 22300, 22400, 22500, 22600, 22700, 22800, 22900, 23000, 23100, 23200, 23300, 23400, 23500, 23600, 23700, 23800, 23900, 24000, 24100, 24200, 24300, 24400, 24500, 24600, 24700, 24800, 24900, 25000, 25100, 25200, 25300, 25400, 25500, 25600, 25700, 25800, 25900, 26000, 26100, 26200, 26300, 26400, 26500, 26600, 26700, 26800, 26900, 27000, 27100, 27200, 27300, 27400, 27500, 27600, 27700, 27800, 27900, 28000, 28100, 28200, 28300, 28400, 28500, 28600, 28700, 28800, 28900, 29000, 29100, 29200, 29300, 29400, 29500, 29600, 29700, 29800, 29900, 30000, 30100, 30200, 30300, 30400, 30500, 30600, 30700, 30800, 30900, 31000, 31100, 31200, 31300, 31400, 31500, 31600, 31700, 31800, 31900, 32000, 32100, 32200, 32300, 32400, 32500, 32600, 32700, 32800, 32900, 33000, 33100, 33200, 33300, 33400, 33500, 33600, 33700, 33800, 33900, 34000, 34100, 34200, 34300, 34400, 34500, 34600, 34700, 34800, 34900, 35000, 35100, 35200, 35300, 35400, 35500, 35600, 35700, 35800, 35900, 36000, 36100, 36200, 36300, 36400, 36500, 36600, 36700, 36800, 36900, 37000, 37100, 37200, 37300, 37400, 37500, 37600, 37700, 37800, 37900, 38000, 38100, 38200, 38300, 38400, 38500, 38600, 38700, 38800, 38900, 39000, 39100, 39200, 39300, 39400, 39500, 39600, 39700, 39800, 39900, 40000, 40100, 40200, 40300, 40400, 40500, 40600, 40700, 40800, 40900, 41000, 41100, 41200, 41300, 41400, 41500, 41600, 41700, 41800, 41900, 42000, 42100, 42200, 42300, 42400, 42500, 42600, 42700, 42800, 42900, 43000, 43100, 43200, 43300, 43400, 43500, 43600, 43700, 43800, 43900, 44000, 44100, 44200, 44300, 44400, 44500, 44600, 44700, 44800, 44900, 45000, 45100, 45200, 45300, 45400, 45500, 45600, 45700, 45800, 45900, 46000, 46100, 46200, 46300, 46400, 46500, 46600, 46700, 46800, 46900, 47000, 47100, 47200, 47300, 47400, 47500, 47600, 47700, 47800, 47900, 48000, 48100, 48200, 48300, 48400, 48500, 48600, 48700, 48800, 48900, 49000, 49100, 49200, 49300, 49400, 49500, 49600, 49700, 49800, 49900, 50000, 50100, 50200, 50300, 50400, 50500, 50600, 50700, 50800, 50900, 51000, 51100, 51200, 51300, 51400, 51500, 51600, 51700, 51800, 51900, 52000, 52100, 52200, 52300, 52400, 52500, 52600, 52700, 52800, 52900, 53000, 53100, 53200, 53300, 53400, 53500, 53600, 53700, 53800, 53900, 54000, 54100, 54200, 54300, 54400, 54500, 54600, 54700, 54800, 54900, 55000, 55100, 55200, 55300, 55400, 55500, 55600, 55700, 55800, 55900, 56000, 56100, 56200, 56300, 56400, 56500, 56600, 56700, 56800, 56900

Scale:  $1'' = 50'$



Scale: Vert. 1" = 10'  
Horiz. 1" = 20'

## INDEX

SHEET 2/7

STATE OF CALIFORNIA  
DEPARTMENT OF PUBLIC WORKS  
DIVISION OF HIGHWAYS

GYPSUM CANYON ROAD  
UNDERCROSSING

LOG OF TEST BORINGS

SCALE <i>As Noted</i>	BRIDGE <i>55-506</i> %	FILL	DRAWING <i>55506-7</i>
-----------------------	------------------------	------	------------------------

AS BUILT PLANS

Contract No. 07-040024  
Date Completed \_\_\_\_\_  
Document No. 70065928

Charge	07210
W. A.	040021


Disregard price books of earlier numbers

→ PREL. DRAWING NO. PRE

I HEREBY CERTIFY THAT THIS IS A TRUE AND ACCURATE COPY OF THE ABOVE DOCUMENT TAKEN UNDER MY DIRECTION AND CONTROL ON THIS DATE IN SACRAMENTO, CALIFORNIA PURSUANT TO AUTHORIZATION BY THE DIRECTOR OF PUBLIC WORKS.

DATE 6-1-73 SIGNATURE Wm. F. Galt TITLE SA RMC





**NOTES:**



- THE BORING LOGS AND RELATED INFORMATION REPRESENT THE OPINION OF THE GEOTECHNICAL ENGINEER AS TO THE CHARACTER OF THE MATERIALS AT THE LOCATIONS SHOWN. SOIL AND GROUNDWATER CONDITIONS BETWEEN ADJACENT TEST HOLES AND AT OTHER LOCATIONS MAY DIFFER FROM THOSE SHOWN. GROUNDWATER CONDITIONS MAY CHANGE WITH PASSAGE OF TIME. ALL LOCATIONS AND ELEVATIONS ARE APPROXIMATE.
- AUGER BORINGS WERE DRILLED WITH A CME 75 DRILL RIG.
- ELEVATIONS ARE BASED ON TOPOGRAPHIC BASE SHEET MAPING PREPARED FOR THIS PROJECT. TEST BORING ELEVATIONS ARE IN FEET AND ARE REFERENCED TO MEAN SEA LEVEL DATUM.
- DETAILED BORING LOGS ARE INCLUDED IN THE JULY 1990 GEOTECHNICAL BRIDGE FOUNDATION REPORT PREPARED BY CH2M HILL, FILE NO. LA028364.ELI.
- ELEVATIONS SHOWN ARE BASED UPON OCS DATUM 1976.
- BASIS OF BEARINGS IS CALIFORNIA STATE PLANE COORDINATE SYSTEM (1983 N.A.D.).

**BENCH MARK**  
3R-71-71  
(PM R 16.4)

**DESCRIPTION**  
STD. OCS BM DISK SET IN TOP OF A PCC HOWL FOR A BOX CULVERT, IN THE SE'LY QUAD OF THE INTERS. OF RTE-91 AND GYPSUM CYN. RD., 265 FT. SO. OF THE SO. EDGE OF THE FWY. BRIDGE, 60 FT. SE'LY OF THE E. EDGE OF THE ON-RAMP ROAD OF THE FWY, 1 FT. W'LY OF THE E'LY END OF THE HOWL, LEVEL WITH THE ROAD.  
(OCS VERT. CON. REV. 1986 PG 09-2)  
(PSOMAS SR 89-03 PG-152)

7. INDICATES BOTTOM OF FOOTING ELEVATION. FOR PILE LAYOUT SEE OTHER SHEETS.

**ELEVATION**  
397.861



DIST	COUNTY	ROUTE	POST MILES TOTAL PROJECT	SHEET NO.	TOTAL SHEETS
12	Oran	91	RI0.1/RI8.9		


REGISTERED ENGINEER-GEOTECHNICAL

PLANS APPROVAL DATE

ORANGE COUNTY TRANSP. COMM.  
1055 N. MAIN ST., SUITE 516  
SANTA ANA, CALIFORNIA 92701

CH2M HILL  
2510 RED HILL AVE, SUITE A  
SANTA ANA, CALIFORNIA 92705

REGISTERED PROFESSIONAL ENGINEER  
Stuart Whitman  
No. CE 896  
Exp. 12/31/92  
STATE OF CALIFORNIA



DESIGN OVERSIGHT		DRAWN BY		E. M. SMITH		APPROVAL RECOMMENDED BY		L. PERKO		BRIDGE NO.		55-506 R/L		GYPSUM CANYON ROAD U.C. (WIDEN)	
SIGN OFF DATE		CHECKED BY		E. M. SMITH		REGISTRATION NO.		REGISTRATION NO.		KENT CORDTZ		PROJECT ENGINEER		LOG OF TEST BORINGS	
3/6/92						CE44359		CE44359		12-926004		16.40			
										DISREGARD PRINTS BEARING EARLIER REVISION DATES		REVISION DATES (PRELIMINARY STAGE ONLY)		SHEET 8 OF 9	









LEGEND OF BORING OPERATIONS


IN-SITU, LAB & FIELD TEST DESIGNATIONS

TYPE OF BORINGS

LEGEND FOR EARTH MATERIALS (USCS)

CONSISTENCY CLASSIFICATION FOR SOILS

NOTE: Visual classification of earth materials are based on field inspection and are confirmed or revised with laboratory test results as necessary.



Dist 12 COUNTY Ora ROUTE 241 POST MILES TOTAL PROJECT 35.1-38.1 SHEET No. 218 TOTAL SHEETS 220

REGISTERED GEOTECHNICAL ENGINEER DATE 6/20/08

PLANS APPROVAL DATE

THE STATE OF CALIFORNIA OR ITS OFFICERS OR AGENTS SHALL NOT BE RESPONSIBLE FOR THE ACCURACY OR COMPLETENESS OF ELECTRONIC COPIES OF THIS PLAN SHEET.

DIAZ YOURMAN & ASSOCIATES 1616 E. 17TH STREET SANTA ANA, CA 92705

PARSONS 2201 DUPONT DRIVE SUITE 200 IRVINE, CA 92612

UNLESS OTHERWISE NOTED, ALL COORDINATE DISTANCES AND BEARINGS ARE BASED ON THE CALIFORNIA COORDINATE SYSTEM (CCS83), ZONE VI, 1983 NAD (1988 EPOCH) USING SR 241 CONSTRUCTION SURVEY CONTROL POINTS 778 AND 795 AS SHOWN ON AS BUILT DRAWINGS.

ELEVATIONS (NGVD 29, OCS 1976 ADJUSTMENT) ARE BASED ON THE FOLLOWING CONSTRUCTION SURVEY CONTROL POINTS:

POINT 778 IS A FOUND BRASS CAP STAMPED 778 ELEV = 968.32 FEET

POINT 795 IS A FOUND ORANGE COUNTY SURVEYOR'S 2 1/2" BRASS DISK STAMPED EBM-99 9-88 ELEV = 652.034 FEET

NO AS BUILT CHANGES AS BUILT CORRECTIONS BY CONTRACT NO. K 000383 DATE 03-29-2010

PROFILE VERTICAL 1"=10ft HORIZONTAL 1"=50ft

ALL DIMENSIONS ARE IN FEET UNLESS OTHERWISE SHOWN

WINDY RIDGE WILDLIFE UC (WIDEN)

LOG OF TEST BORINGS 1 OF 3

BRIDGE NO. 55-724R POST MILES 36.7

Jon Hamaguchi DESIGN OVERSIGHT 9/5/08

DRAWN BY J. LEE

CHECKED BY S. SU

FIELD INVESTIGATION BY: T. KOTA January 2007

MICHAEL ENDRES TCA PROJECT ENGINEER

TRANSPORTATION CORRIDOR AGENCY

USERNAME => \$USER DGN FILE => \$REQUEST

CU 12242 EA 060111



## Appendix C

### As-built Maps

***REVISED FINAL***  
**Geotechnical Certification Report**

**Design Section 12 North (Stations 851+00 to 880+00)  
And Design Section 13**

**June 19, 1998  
(Revised October 15, 1999)**

**(Volume I of II)**

P.M. = 36.45 to 38.10, CU. = 12-240, EA. = 111000

---

*Submitted to*

**Transportation Corridor Agencies**

*Submitted by*


**Silverado**  
**CONSTRUCTORS**  
A JOINT VENTURE OF FCI CONSTRUCTORS, SUKUT  
CONSTRUCTION, INC., WAYSS & FREYTAG AND  
OBAYASHI CORPORATION, SUPPORTED BY CH2M HILL



DIST	COUNTY	ROUTE	POST MILES TOTAL PROJECT	SHEET NO.	TOTAL SHEETS
12	Ora	241	33.6 - 38.0	17	512

REGISTERED CIVIL ENGINEER  
 FRANK D. CURRIE  
 No. 45605  
 Exp. 12/31/98  
 PLANS APPROVAL DATE  
 ASL Consulting Engineers  
 ONE JENNER STREET, STE. 200  
 IRVINE, CA 92718

The State of California or its officers or agents shall not be responsible for the accuracy or completeness of electronic copies of this plan sheet.



LINE NAME	LINE DESCRIPTION
*ST* LINE	SOUTHBOUND TOLL PLAZA LINE
*NT* LINE	NORTHBOUND TOLL PLAZA LINE
*A* LINE	ROUTE 241 MAIN LINE

APPROVED FOR CONSTRUCTION	
 Date: 02/19/98	
Silverado	
Date of Approval for Construction: 01/15/98	
DCN: R15290	Section: 11/12

SECTION 12 NORTH

PLATE A

KEY MAP AND LINE INDEX  
 CONTOUR GRADING AND  
 DRAINAGE SHEETS  
 NO SCALE  
 K-2

FOR REDUCED PLANS  
 ORIGINAL SCALE IS IN INCHES

TCA PROJECT MANAGER MICHAEL ENDRES	DATE	REVISION
	1/98	1/98
	5/98	5/98
	6/98	6/98
TOLL ROAD OVERSIGHT	RB	MC
	CALCULATED/DESIGNED BY	CHECKED BY
TRANSPORTATION CORRIDOR AGENCIES		

TRANSPORTATION CORRIDOR AGENCIES	TOLL ROAD OVERSIGHT	TCA PROJECT MANAGER MICHAEL ENDRES	CALCULATED/ DESIGNED BY CHECKED BY	RB MC	DATE 1/88 5/98	REVISED BY DATE REVISION

APPROVED FOR CONSTRUCTION



Date: 11/26/97


Silverado

Date of Approval for Construction: 11/21/97

DCN: R14637
Section: 13


DIST	COUNTY	ROUTE	TOTAL PROJECT MILES	SHEET NO.	TOTAL SHEETS
12	Ora	241/91	38.0-38.3/14.7-17.9	17	602


08-01-96  
REGISTERED CIVIL ENGINEER



PLANS APPROVAL DATE  
CH2M HILL  
3 HUTTON CENTRE DR., #200  
SANTA ANA, CA 92707

The State of California or its officers or agents shall not be responsible for the accuracy or completeness of electronic copies of this plan sheet.



LINE INDEX

LINE NAME	LINE DESCRIPTION
*A* LINE	ETC SR 241
*B* LINE	WB SR 91
*C* LINE	EB SR 91
*SAC* LINE	EXIST SANTA ANA CANYON RD
*ES* LINE	EAST91-SOUTH241 CONNECTOR
*NE* LINE	NORTH241-EAST91 CONNECTOR
*NW* LINE	NORTH241-WEST91 CONNECTOR
*WS* LINE	WEST91-SOUTH241 CONNECTOR
*FSAC* LINE	FUTURE SANTA ANA CANYON RD
*GC* LINE	GYPSUM CANYON ROAD
*GC3* LINE	GYPSUM CANYON WB OFF RAMP

SECTION 13

PLATE B

KEY MAP AND LINE INDEX  
CONTOUR GRADING

NO SCALE

K-2








NOTE: FOR COMPLETE RIGHT OF WAY AND  
ACCURATE ACCESS DATA, SEE RIGHT OF  
WAY RECORD MAPS AT DISTRICT OFFICE.

DIST	COUNTY	ROUTE	POST MILES TOTAL PROJECT	SHEET TOTAL NO. SHEET
12	Oran	241/ 91	38.0-38.3/ 14.7-17.9	



08-01-96  
REGISTERED CIVIL ENGINEER

PLANS APPROVED DATE

CH2M HILL  
3 HUTTON CENTRE DR., #200  
SANTA ANA, CA 92707

REGISTERED PROFESSIONAL ENGINEER  
VANDERLINDE  
No. C46300  
Exp. 12-31-98  
CIVIL  
STATE OF CALIFORNIA

The State of California or its officers or agents shall not be responsible for the accuracy or completeness of electronic copies of this plan sheet.




13-NOV-1996

08:15:00

13G08.dlv

TRANSPORTATION  
CORRIDOR  
AGENCIES




TCA PROJECT MANAGER  
MIKE ENDRES

CALCULATED/  
DESIGNED BY  
ND


REVISOR BY  
DATE  
3/96

CHECKED BY  
MC

DATE REVISED  
3/96



THIS PLAN ACCURATE FOR CONTOUR GRADING ONLY




ETC SECTION 13  
GEOTECHNICAL MAP  
PLATE 13  
SCALE: 1" = 50'  
G-8



DIST	COUNTY	ROUTE	POST MILES TOTAL PROJECT	SHEET TOTAL NO. SHEETS
12	Ora	241/91	38.0-38.3/14.7-17.9	

08-01-96  
 REGISTERED CIVIL ENGINEER  
 PLANS APPROVAL DATE  
 CH2M HILL  
 3 HUTTON CENTRE DR., #200  
 SANTA ANA, CA 92707  
 The State of California or its officers or agents shall not be responsible for the accuracy or completeness of electronic copies of this plan sheet.

REGISTERED PROFESSIONAL ENGINEER  
 J. VANDERLINDE  
 No. C46300  
 Exp. 12-31-98  
 STATE OF CALIFORNIA



08-OCT-1987

09-57-00

13-09-01

08-OCT-1987

09-57-00

13-09-01

08-OCT-1987

09-57-00

13-09-01

THIS PLAN ACCURATE FOR CONTOUR GRADING ONLY

ETC SECTION 13  
 GEOTECHNICAL MAP  
 PLATE 14  
 SCALE: 1" = 50'

2740-224,11 STANDARD 3CL ORDENT (REV. 1/90)

CU

EA 11000



25-NOV-1996

10-03-99

13610.dlv

TRANSPORTATION

CONCORD

AGENCIES

TCA PROJECT MANAGER

MIKE ENDRES

CALCULATED/DESIGNED BY

ND

MC

DATE REVIS

3/96

5/96

DATE REVIS

DIST	COUNTY	ROUTE	POST MILES TOTAL PROJECT	SHEET TOTAL NO. SHEETS
12	Ora	241/91	38.0-38.3/14.7-17.9	

08-01-96

REGISTERED CIVIL ENGINEER

CH2M HILL

3 HUTTON CENTRE DR., #200

SANTA ANA, CA 92707

PLANS APPROVA DATE

12-31-98

REGISTERED PROFESSIONAL ENGINEER

VANDERLINDE


No. C46300

Exp. 12-31-98

CIVIL

SITE OF CALIFORNIA

The State of California or its officers or agents shall not be responsible for the accuracy or completeness of electronic copies of this plan sheet.





17-OCT-1996

10:34:48

13g11.dlv

TRANSPORTATION CORRIDOR AGENCIES

TCA PROJECT MANAGER

MIKE ENDRES

CALCULATED/DESIGNED BY

ND

CHECKED BY

MC

DATE REVISED BY

3/96

DATE REVISED

5/96

DIST	COUNTY	ROUTE	POST MILES TOTAL PROJECT	SHEET TOTAL NO. SHEETS
12	Ora	241/91	38.0-38.3/14.7-17.9	

08-01-96

REGISTERED CIVIL ENGINEER

PLANS APPROVAL DATE

CH2M HILL

3 HUTTON CENTRE DR., #200

SANTA ANA, CA 92707

PROFESSIONAL ENGINEER


L. VANDERLINDE

No. C46300

Exp. 12-31-98

STATE OF CALIFORNIA

The State of California or its officers or agents shall not be responsible for the accuracy or completeness of electronic copies of this plan sheet.



THIS PLAN ACCURATE FOR CONTOUR GRADING ONLY

FOR REDUCED PLANS  
ORIGINAL SCALE IS 1" = 50'

ETC SECTION 13  
GEOTECHNICAL MAP  
PLATE 16  
SCALE: 1" = 50'

G-11







17-OCT-1998

10:40:38

13g13.dlv

TRANSPORTATION

CONTRON

AGENCIES

TCA PROJECT MANAGER

MIKE ENDRES


CALCULATED/DESIGNED BY

ND 3/96

MC 5/96

DATE REVISED BY

DATE REVISED




DIST	COUNTY	ROUTE	POST MILES TOTAL PROJECT	SHEET TOTAL NO. SHEET
12	Ora	241/91	38.0-38.3/14.7-17.9	

08-01-96  
 REGISTERED CIVIL ENGINEER  
 PLANS APPROVAL DATE  
 CH2M HILL  
 3 HUTTON CENTRE DR., #200  
 SANTA ANA, CA 92707  
 The State of California or its officers or agents shall not be responsible for the accuracy or completeness of electronic copies of this plan sheet.

REGISTERED PROFESSIONAL ENGINEER  
 VANDERLINDE  
 No. C46300  
 Exp. 12-31-98  
 CIVIL  
 STATE OF CALIFORNIA

THIS PLAN ACCURATE FOR CONTOUR GRADING ONLY





06-NOV-1996

12:00:20

13g15.dlv

TRANSPORTATION  
CORRIDOR  
AGENCIES

TCA PROJECT MANAGER

MIKE ENDRES

CALCULATED/  
DESIGNED BY

CHECKED BY


DATE  
3/96

REVISOR  
MC

DATE  
5/96

REVISOR  
MC

DATE  
5/96



THIS PLAN ACCURATE FOR CONTOUR GRADING ONLY

FOR REDUCED PLANS  
ORIGINAL SCALE IS 1" = 50'

DIST	COUNTY	ROUTE	POST MILES TOTAL PROJECT	SHEET TOTAL NO. SHEETS
12	Ora	241/ 91	38.0-38.3/ 14.7-17.9	

*R. Vanderlinde* 08-01-96  
REGISTERED CIVIL ENGINEER

PLANS APPROVAL DATE

CH2M HILL  
3 HUTTON CENTRE DR., #200  
SANTA ANA, CA 92707

The State of California or its officers or agents shall not be responsible for the accuracy or completeness of electronic copies of this plan sheet.

REGISTERED PROFESSIONAL ENGINEER  
VANDERLINDE  
No. C46300  
Exp. 12-31-98  
CIVIL  
STATE OF CALIFORNIA

ETC SECTION 13  
GEOTECHNICAL MAP  
PLATE 20  
SCALE: 1" = 50'

G-15

CU

EA 110000







12-NOV-1998

13:48:05

13g17.dlv

TRANSPORTATION

CORRIDOR

AGENCIES

TCA PROJECT MANAGER

MIKE ENDRES

CALCULATED/DESIGNED BY

ND

MC

DATE

3/98


5/98

REVISED BY

DATE

5/98

REVISED



DIST	COUNTY	ROUTE	POST MILES	SHEET TOTAL
12	Ora	241/91	38.0-38.3/14.7-17.9	NO. SHEETS

08-01-96

REGISTERED CIVIL ENGINEER

CH2M HILL

3 HUTTON CENTRE DR., #200

SANTA ANA, CA 92707

PLANS APPROVA DATE

CH2M HILL

3 HUTTON CENTRE DR., #200

SANTA ANA, CA 92707

THE STATE OF CALIFORNIA OR ITS OFFICERS OR AGENTS SHALL NOT BE RESPONSIBLE FOR THE ACCURACY OR COMPLETENESS OF ELECTRONIC COPIES OF THIS PLAN SHEET.

ETC SECTION 13

GEOTECHNICAL MAP

PLATE 22

SCALE: 1" = 50'

G-17







04-NOV-1996

13-58:01

13g20.dlv

TRANSPORTATION

CORRIDOR

AGENCIES

TCA PROJECT MANAGER

MIKE ENDRES

CALCULATED/DESIGNED BY

ND

MC

DATE

3/96


5/96

REVISED BY

DATE

REVISED BY

DATE



DIST	COUNTY	ROUTE	POST MILES TOTAL PROJECT	SHEET TOTAL NO. SHEETS
12	Ora	241/91	38.0-38.3/14.7-17.9	

08-01-96

REGISTERED CIVIL ENGINEER

PLANS APPROVAL DATE

CH2M HILL

3 HUTTON CENTRE DR., #200

SANTA ANA, CA 92707

REGISTERED PROFESSIONAL ENGINEER


L. VANDERLINDE

No. C46300

Exp. 12-31-98

STATE OF CALIFORNIA



CIVIL



ETC SECTION 13  
 GEOTECHNICAL MAP  
 PLATE 25  
 SCALE: 1" = 50'



Appendix D  
Caltrans Acceleration  
Response Spectra





**SITE DATA (ARS Online Version 2.3.06)**

<b>Shear Wave Velocity, <math>V_{s30}</math>:</b>	270 m/s
<b>Latitude:</b>	33.864291
<b>Longitude:</b>	-117.716789
<b>Depth to <math>V_s = 1.0</math> km/s:</b>	N/A
<b>Depth to <math>V_s = 2.5</math> km/s:</b>	N/A

**DETERMINISTIC****Elsinore (Glen Ivy) rev**

<b>Fault ID:</b>	365
<b>Maximum Magnitude (MMax):</b>	7.7
<b>Fault Type:</b>	SS
<b>Fault Dip:</b>	90 Deg
<b>Dip Direction:</b>	V
<b>Bottom of Rupture Plane:</b>	13.00 km
<b>Top of Rupture Plane(<math>Z_{tor}</math>):</b>	0.00 km
<b>Rrup</b>	4.46 km
<b>Rjb:</b>	4.46 km
<b>Rx:</b>	2.40 km
<b>Fnorm:</b>	0
<b>Frev:</b>	0

<b>Period</b>	<b>SA(Base Spectrum)</b>	<b>Basin Factor</b>	<b>Near Fault Factor(Applied)</b>	<b>SA(Final Spectrum)</b>
<b>0.01</b>	0.426	1.000	1.000	0.426
<b>0.05</b>	0.500	1.000	1.000	0.500
<b>0.1</b>	0.641	1.000	1.000	0.641
<b>0.15</b>	0.750	1.000	1.000	0.750
<b>0.2</b>	0.823	1.000	1.000	0.823
<b>0.25</b>	0.856	1.000	1.000	0.856
<b>0.3</b>	0.869	1.000	1.000	0.869
<b>0.4</b>	0.867	1.000	1.000	0.867
<b>0.5</b>	0.864	1.000	1.000	0.864
<b>0.6</b>	0.824	1.000	1.040	0.857
<b>0.7</b>	0.789	1.000	1.080	0.852
<b>0.85</b>	0.735	1.000	1.140	0.838
<b>1</b>	0.684	1.000	1.200	0.821
<b>1.2</b>	0.619	1.000	1.200	0.743
<b>1.5</b>	0.540	1.000	1.200	0.648
<b>2</b>	0.431	1.000	1.200	0.517
<b>3</b>	0.285	1.000	1.200	0.342
<b>4</b>	0.207	1.000	1.200	0.248
<b>5</b>	0.161	1.000	1.200	0.194

**Elsinore fault zone (Whittier section)**

**Fault ID:** 352  
**Maximum Magnitude (MMax):** 6.9  
**Fault Type:** SS  
**Fault Dip:** 75 Deg  
**Dip Direction:** ne  
**Bottom of Rupture Plane:** 14.50 km  
**Top of Rupture Plane(Ztor):** 0.00 km  
**Rrup** 1.83 km  
**Rjb:** 1.83 km  
**Rx:** 1.83 km  
**Fnorm:** 0  
**Frev:** 0

Period	SA(Base Spectrum)	Basin Factor	Near Fault Factor(Applied)	SA(Final Spectrum)
0.01	0.466	1.000	1.000	0.466
0.05	0.543	1.000	1.000	0.543
0.1	0.671	1.000	1.000	0.671
0.15	0.776	1.000	1.000	0.776
0.2	0.857	1.000	1.000	0.857
0.25	0.901	1.000	1.000	0.901
0.3	0.920	1.000	1.000	0.920
0.4	0.931	1.000	1.000	0.931
0.5	0.915	1.000	1.000	0.915
0.6	0.859	1.000	1.040	0.893
0.7	0.810	1.000	1.080	0.875
0.85	0.734	1.000	1.140	0.836
1	0.663	1.000	1.200	0.796
1.2	0.580	1.000	1.200	0.696
1.5	0.485	1.000	1.200	0.581
2	0.365	1.000	1.200	0.438
3	0.226	1.000	1.200	0.272
4	0.157	1.000	1.200	0.188
5	0.118	1.000	1.200	0.142

**Elsinore fault zone (Chino section)**

**Fault ID:** 355  
**Maximum Magnitude (MMax):** 6.6  
**Fault Type:** SS  
**Fault Dip:** 50 Deg  
**Dip Direction:** SW  
**Bottom of Rupture Plane:** 9.20 km  
**Top of Rupture Plane(Ztor):** 0.00 km  
**Rrup** 6.13 km  
**Rjb:** 0.29 km  
**Rx:** 8.01 km



**Fnorm:** 0  
**Frev:** 0

<b>Period</b>	<b>SA(Base Spectrum)</b>	<b>Basin Factor</b>	<b>Near Fault Factor(Applied)</b>	<b>SA(Final Spectrum)</b>
<b>0.01</b>	0.533	1.000	1.000	0.533
<b>0.05</b>	0.635	1.000	1.000	0.635
<b>0.1</b>	0.815	1.000	1.000	0.815
<b>0.15</b>	0.941	1.000	1.000	0.941
<b>0.2</b>	1.007	1.000	1.000	1.007
<b>0.25</b>	1.025	1.000	1.000	1.025
<b>0.3</b>	1.022	1.000	1.000	1.022
<b>0.4</b>	0.986	1.000	1.000	0.986
<b>0.5</b>	0.922	1.000	1.000	0.922
<b>0.6</b>	0.833	1.000	1.040	0.866
<b>0.7</b>	0.760	1.000	1.080	0.821
<b>0.85</b>	0.665	1.000	1.140	0.758
<b>1</b>	0.584	1.000	1.200	0.701
<b>1.2</b>	0.494	1.000	1.200	0.593
<b>1.5</b>	0.394	1.000	1.200	0.473
<b>2</b>	0.263	1.000	1.200	0.316
<b>3</b>	0.130	1.000	1.200	0.156
<b>4</b>	0.079	1.000	1.200	0.095
<b>5</b>	0.059	1.000	1.200	0.070

## PROBABILISTIC

<b>Probabilistic Model</b>				
<b>USGS Seismic Hazard Map(2008) 975 Year Return Period</b>				
<b>Period</b>	<b>SA(Base Spectrum)</b>	<b>Basin Factor</b>	<b>Near Fault Factor(Applied)</b>	<b>SA(Final Spectrum)</b>
<b>0.01</b>	0.631	1.000	1.000	0.631
<b>0.05</b>	0.916	1.000	1.000	0.916
<b>0.1</b>	1.075	1.000	1.000	1.075
<b>0.15</b>	1.216	1.000	1.000	1.216
<b>0.2</b>	1.328	1.000	1.000	1.328
<b>0.25</b>	1.335	1.000	1.000	1.335
<b>0.3</b>	1.340	1.000	1.000	1.340
<b>0.4</b>	1.266	1.000	1.000	1.266
<b>0.5</b>	1.212	1.000	1.000	1.212
<b>0.6</b>	1.115	1.000	1.040	1.160
<b>0.7</b>	1.040	1.000	1.080	1.123
<b>0.85</b>	0.922	1.000	1.140	1.051
<b>1</b>	0.821	1.000	1.200	0.985
<b>1.2</b>	0.700	1.000	1.200	0.839
<b>1.5</b>	0.575	1.000	1.200	0.691

<b>2</b>	0.447	1.000	1.200	0.537
<b>3</b>	0.282	1.000	1.200	0.338
<b>4</b>	0.199	1.000	1.200	0.239
<b>5</b>	0.161	1.000	1.200	0.193

## MINIMUM DETERMINISTIC SPECTRUM

<b>Period</b>	<b>SA</b>
<b>0.01</b>	0.226
<b>0.05</b>	0.275
<b>0.1</b>	0.400
<b>0.15</b>	0.481
<b>0.2</b>	0.505
<b>0.25</b>	0.499
<b>0.3</b>	0.486
<b>0.4</b>	0.446
<b>0.5</b>	0.400
<b>0.6</b>	0.350
<b>0.7</b>	0.311
<b>0.85</b>	0.265
<b>1</b>	0.230
<b>1.2</b>	0.192
<b>1.5</b>	0.152
<b>2</b>	0.107
<b>3</b>	0.064
<b>4</b>	0.043
<b>5</b>	0.032

## Envelope Data

<b>Period</b>	<b>SA</b>
<b>0.01</b>	0.631
<b>0.05</b>	0.916
<b>0.1</b>	1.075
<b>0.15</b>	1.216
<b>0.2</b>	1.328
<b>0.25</b>	1.335
<b>0.3</b>	1.340
<b>0.4</b>	1.266
<b>0.5</b>	1.212
<b>0.6</b>	1.160
<b>0.7</b>	1.123
<b>0.85</b>	1.051
<b>1</b>	0.985
<b>1.2</b>	0.839
<b>1.5</b>	0.691




2	0.537
3	0.342
4	0.248
5	0.194

## Appendix E

### Soil Survey Data




K Factor, Whole Soil—Orange County and Part of Riverside County, California  
(SR241/91 Direct Connector)



K Factor, Whole Soil—Orange County and Part of Riverside County, California  
(SR241/91 Direct Connector)















## MAP LEGEND

### Area of Interest (AOI)







 Area of Interest (AOI)










### Soils

#### Soil Rating Polygons
















	.02
	.05
	.10
	.15
	.17
	.20
	.24
	.28
	.32
	.37
	.43
	.49
	.55
	.64
	Not rated or not available

#### Soil Rating Lines








	.02
	.05
	.10
	.15
	.17
	.20

	.24
	.28
	.32
	.37
	.43
	.49
	.55
	.64
	Not rated or not available

#### Soil Rating Points

	.02
	.05
	.10
	.15
	.17
	.20
	.24
	.28
	.32
	.37
	.43
	.49
	.55
	.64
	Not rated or not available

#### Water Features

	Streams and Canals
	Rails
	Interstate Highways
	US Routes
	Major Roads
	Local Roads
	Aerial Photography

## MAP INFORMATION

The soil surveys that comprise your AOI were mapped at 1:24,000.

Please rely on the bar scale on each map sheet for map measurements.

Source of Map: Natural Resources Conservation Service  
Web Soil Survey URL: <http://websoilsurvey.nrcs.usda.gov>  
Coordinate System: Web Mercator (EPSG:3857)

Maps from the Web Soil Survey are based on the Web Mercator projection, which preserves direction and shape but distorts distance and area. A projection that preserves area, such as the Albers equal-area conic projection, should be used if more accurate calculations of distance or area are required.

This product is generated from the USDA-NRCS certified data as of the version date(s) listed below.

Soil Survey Area: Orange County and Part of Riverside County, California

Survey Area Data: Version 8, Sep 19, 2014

Soil map units are labeled (as space allows) for map scales 1:50,000 or larger.

Date(s) aerial images were photographed: May 3, 2010—Jul 3, 2010

The orthophoto or other base map on which the soil lines were compiled and digitized probably differs from the background imagery displayed on these maps. As a result, some minor shifting of map unit boundaries may be evident.



## K Factor, Whole Soil

K Factor, Whole Soil— Summary by Map Unit — Orange County and Part of Riverside County, California (CA678)				
Map unit symbol	Map unit name	Rating	Acres in AOI	Percent of AOI
106	Anaheim loam, 15 to 30 percent slopes	.32	0.1	0.0%
107	Anaheim loam, 30 to 50 percent slopes	.32	14.0	2.2%
134	Calleguas clay loam, 50 to 75 percent slopes, eroded	.32	24.1	3.7%
145	Cieneba-Rock outcrop complex, 30 to 75 percent slopes	.28	121.0	18.7%
146	Corralitos loamy sand	.15	22.0	3.4%
163	Metz loamy sand	.20	112.4	17.3%
175	Myford sandy loam, 9 to 15 percent slopes	.37	3.5	0.5%
185	Pits		0.5	0.1%
191	Riverwash	.02	42.7	6.6%
192	Rock outcrop-Cieneba complex, 30 to 75 percent slopes		28.5	4.4%
193	San Andreas sandy loam, 15 to 30 percent slopes	.20	38.5	5.9%
197	Soboba gravelly loamy sand, 0 to 5 percent slopes	.05	3.4	0.5%
198	Soboba cobbly loamy sand, 0 to 15 percent slopes	.05	15.5	2.4%
199	Soper loam, 15 to 30 percent slopes	.37	1.5	0.2%
200	Soper loam, 30 to 50 percent slopes	.37	82.7	12.8%
202	Soper gravelly loam, 30 to 50 percent slopes	.17	63.1	9.7%
204	Soper-Rock outcrop complex, 30 to 75 percent slopes	.17	15.9	2.5%
210	Thapto-Histic Fluvaquents	.15	0.7	0.1%
224	Yorba cobbly sandy loam, 9 to 30 percent slopes	.15	6.9	1.1%

K Factor, Whole Soil— Summary by Map Unit — Orange County and Part of Riverside County, California (CA678)				
Map unit symbol	Map unit name	Rating	Acres in AOI	Percent of AOI
226	Yorba cobbly sandy loam, 30 to 50 percent slopes	.10	51.4	7.9%
<b>Totals for Area of Interest</b>			<b>648.3</b>	<b>100.0%</b>

## Description

Erosion factor K indicates the susceptibility of a soil to sheet and rill erosion by water. Factor K is one of six factors used in the Universal Soil Loss Equation (USLE) and the Revised Universal Soil Loss Equation (RUSLE) to predict the average annual rate of soil loss by sheet and rill erosion in tons per acre per year. The estimates are based primarily on percentage of silt, sand, and organic matter and on soil structure and saturated hydraulic conductivity (Ksat). Values of K range from 0.02 to 0.69. Other factors being equal, the higher the value, the more susceptible the soil is to sheet and rill erosion by water.

"Erosion factor Kw (whole soil)" indicates the erodibility of the whole soil. The estimates are modified by the presence of rock fragments.

## Rating Options

*Aggregation Method:* Dominant Condition

*Component Percent Cutoff:* None Specified

*Tie-break Rule:* Higher

*Layer Options (Horizon Aggregation Method):* Surface Layer (Not applicable)